

Mail

Franklin County Health Department
Division of Environmental Health
107 Industrial Drive-Suite C
Louisburg, North Carolina 27549

PAGE 1 OF 2

Phone: 919-496-8100

SEPTIC PERMIT

Fax: 919-496-8136

Permit Number: 8308 Type: I PIN: 1832-49-7090 Date: 9/2/2015

Applicant: CAMBRIDGE CLASSIC HOMES LL Owner: PRINCETON MANOR WAY
2519 VILLAGE MANOR WAY
RALEIGH, NC 27614

Telephone: (919) 730-6277 Telephone:

Subdivision: PRINCETON MANOR Lot Number: 4 Size: 0.970

Physical Address/ Location /Directions 15 PRINCETON MANOR DR

Description: LifeTime _____ 5 Year ☒

TYPE FACIL Res # EMPLOY _____ # BEDRMS 3 GPD 360 LTAR 1.3

TYPE WAT County TYPE SYS PtoA TYPE REP PtoA BSMT No BST FX NIA

SIZE TANK 1000 SIZE CHB 1000 SIZE NTR 3'x29' MTD 24"

COMMENTS: Install system as designed by CCSC
Pump to P. Manifold

Septic Contractors are responsible for notifying the health department for final inspections, between 8:00-9:00 AM on the day of completion, Monday - Friday. Any request for final inspections received afterwards will be scheduled the same day, if possible, or the next workday. Have permit number and owner/applicant's name ready when making the call.

Actions of representatives of state or local agencies engaged in the evaluation and determination of measures required to effect the compliance with the provisions of this permit shall in no way be taken as a guarantee that wastewater disposal systems permitted and approved will function in a satisfactory manner for any given period of time, or that such employees assume any liability for damages, consequential or direct which are caused, or may be caused, by a malfunction of this wastewater treatment and disposal system.

Proper precautions must be taken to assure the proper functioning of the system after it has been covered. Do not run any heavy equipment over the system, as soft earth will allow damage to the tank and lines. Pipe all roof drains away from the septic system site to prevent flooding of the lines from surface water. Terrace the ground to prevent excessive drainage from higher areas adjacent to the system. Do not construct driveways over any part of the septic system unless proper provisions were made when the septic system was constructed. Only grass, not trees or shrubbery, should be cultivated over the lines. All plumbing fixtures should be carefully inspected periodically and any problems repaired immediately. All septic tanks should be pumped off by a permitted pump operator on a regular schedule, not to exceed every five years.

The improvement permit and construction authorization is a site approval, for the future installation of a wastewater treatment and disposal system. Changes in ownership of the site do not affect the validity of this permit. However, any alteration of the site or soil conditions, changes in the location of the proposed facility, changes to the wastewater flow and/or characteristics, or submittal of false information with the application or misrepresentation of the property lines may subject this permit to suspension or revocation.

FOR THIS TO BE A VALID CONSTRUCTION AUTHORIZATION, A LAYOUT SHEET MUST BE ATTACHED

IMPROVEMENT PERMIT DATE 9/4/15 EHS Shad Feenach

CONSTRUCTION AUTHORIZATION DATE 9/4/15 EHS Shad Feenach

Visit www.franklincountyenvironmentalhealth.com for permit information and tracking.

Pump Fee 3-8-16 W. O. O.

Franklin County Health Department

Name: CAMBRIDGE CLASS

Permit Number

8308

CONTRACTOR

Quality Landscapes

TANK MANU

*PT Mills 1000**PT Mills 1000*

MANU DATE

*11/10/15**10/17/15*

WELL INSTALLED

YES

NO

X

SYSTEM CODE

EZ-203-N-P

SEPTIC SYSTEM LAYOUT

(SKETCH SYSTEM LAYOUT HERE)

See attached Layout + Tap Chart

*✓ 1' d Tanks
1-20-16 SEL*

*✓ 1' d Lines 1-21-16
need to install
1/2" 40" tap on
lowest line*

✓ 1' d pump + Alarm 3/7/16

** Gas line will
need to be rerouted
prior to repair being installed*

SEPTIC SYSTEM AS-BUILT

(IF DIFFERENT FROM INITIAL LAYOUT)

ON REVERSE

OPERATIONS PERMIT

DATE

3/8/16

EHS

Shad Leonard

Cambridge Classic Homes
3-Bedroom Septic System Layout
Princeton Manor Subdivision
Lot 4
Franklin County, NC

N 05°03'10" E

72.52'

LOT 4
42,226 S.F.
0.969 ACRES

System: HHHHHH
Repair: ———

System: Pressure Manifold
Lines: 1-6, (399') 299'
0.3 Soil LTAR
24" Trench Bottom
Accepted Status System

Repair: Pressure Manifold
Lines: 7-13, (330')
0.3 Soil LTAR
24" Trench Bottom
Accepted Status System

RELOCATED
90' WAKE ELECTRIC UTILITY EASEMENT

RELOCATED
50' WAKE ELECTRIC UTILITY EASEMENT

LOT 5

N 55°58'19" E 328.10'

100' WAKE ELECTRIC UTILITY
EASEMENT TO BE ABANDONED
RELOCATION SHOWN

HOLDEN ROAD N.C.S.R. 1147

20' PUBLIC DRAINAGE EASEMENT

S 04°13'47" E 143.62'

PRINCETON
MANOR DR

*Keep Tanks and Drain Lines 10'
from property lines.
*Not a Survey
*Not a Permit

GRAPHIC SCALE
1" = 50'



Central Carolina
Soil Consulting
919-569-6704
Project # 1791