



- *Keep tanks and drain lines 10' from property lines.
- *Not a survey.
- *Keep supply lines >5' from property lines.
- *Some lines are flagged longer in the field than lengths indicate.
- *No grading septic area.

System:	-----
Repair:	-----
Boring:	●
ST	: 1000 Gallon

System: Gravity to D-Box Lines: 1-5, (450') Accepted Status System 0.3 Soil LTAR 24" Trench Bottom
Repair: Gravity to Serial Dist. Lines: 6-10, (450') Accepted Status System 0.3 Soil LTAR 20" Trench Bottom



Central Carolina Soil Consulting, PLLC
1900 South Main Street, Suite 110
Wake Forest, North Carolina 27587
Phone (919)569-6704 Fax (919)569-6703

4-Bedroom Septic Layout
Lot 13, Sorrell Oaks Subdivision
Franklin County, North Carolina

Job# : 4854
Drawn By : LW
Date : 08/25/2023
Revision: 02/24/2024