



OPERATION PERMIT

Franklin County Health Department
107 Industrial Drive
Louisburg, NC 27549
Phone:

For Office Use Only

*CDP File Number 393105 - 1
County ID Number: 2900-85-1392
Evaluated For: REPAIR

Property Owner: CHARLES MORGAN
Owner Address: 364 OPIE FRAZIER RD

City: HENDERSON
State/Zip: NC/ 27537
Phone #:
Address: 402 OPIE FRAZIER RD
HENDERSON, NC 27537

Road #:
Township:
Subdivision:
Phase : NEW Lot:

Structure: SINGLE FAMILY
of Bedrooms: 3
of People:
Water Supply: EXISTING WELL
Saprolite System?: ☐ Yes ☒ No
Pump Required?: ☐ Yes ☒ No
Design Flow: 360
System Classification/Description: TYPE III G. OTHER
NON-CONV. TRENCH SYSTEMS

Installer: *Waste water Solutions*

Certification #:

Specific System EZFLOW EZ 1203H-GEO
Installed:

Septic Tank Date: _____

STB: 2152

Pump Tank Date: _____

PT:

Comments:

This system has been installed in compliance with applicable NC General Statutes, Rules for Sewage Treatment and Disposal, and all conditions of the Improvement Permit and Construction Authorization.

PERMIT CONDITIONS:

- I. Performance: System shall perform in accordance with Rule .1961.
- II. Monitoring: As required by Rule .1961.
- III. Maintenance: Ground absorption sewage treatment and disposal systems shall be checked, and the contents of the septic tank removed, periodically from all compartments, to ensure proper operation of the system. The contents shall be pumped whenever the solids level is found to be more than 1/3 of the liquid depth in any compartment.

Other:

Subsurface Operator Required: ☐ Yes ☒ No

If yes, see attached sheet for additional operation conditions, maintenance and reporting.

Operation:

Other:

Authorized State Agent: Leonard, Shad

Date of Issue: 06/09/2023

Owner/Applicant: _____



File # 393105 PIN# 2900-85-1392

Property Address: 402 Opie Frazier Rd

Applicant or Owner Name: Charles Morgan

Environmental Health Septic/Well Permit Diagram

Building permits cannot be issued nor should construction begin without Construction Authorization issuance.

☐ Septic Improvement Permit ☒ Septic Construction Authorization (CA) ☐ CA Reissue** ☒ As Built
☐ Well Construction Authorization ☐ Additional Diagram/Specifications Attached

Diagram Date**: 4-11-23 EHS: Crystal Eno

**Any previously dated CA diagram is revoked and/or invalid. Confirm this is the valid diagram for the site before beginning any construction.

Installation/grouting inspections may be scheduled the day before, or, the day of installation until 9am by contacting the Environmental Health office at 919 496 8100. A revisit fee may apply if installation is not ready for inspection at the time requested. Septic Operations Permits will be issued after installation is approved, all permits conditions are met, and any outstanding fees are paid. Well Certificate of Completion will be issued after well head approval, all permit conditions are met, and any outstanding fees are paid.

Septic Tank Existing Pump Tank 1 Drainfield 3' x 40' Type System Conv Max Trench Depth 30"

Septic Contractor Wastewater Solutions Septic/Pump tank dates Intelwater 1071 Pump fee? NO YES pd 575-2152

Well Contractor _____ Well Grout date: _____

1000 Gallon ST
6-9-23
SEL

- * Drawing not to scale
- * Check septic tank and d-box for root damage. Replace d-box if needed
- * Check for root damage in beginning of drainlines. If more drainline is needed contact EH.
- * Any foundation must be at least 5' from any part of septic system

* Properly abandon existing tank and install new 1000 gallon septic tank if existing tank is damaged

Future proposed property

