



Construction Authorization

Vance County Health Dept
Environmental Health
115 Charles Rollins Road
Henderson, NC 27536
Phone: (252) 492-5263 Fax: (252) 492-2361

For Office Use Only

*CDP File Number: 383838 - 1
County ID Number: 0536 03043
Evaluated For: NEW

PERMIT VALID UNTIL: 01/31/2028

☐ Open Pump System Sheet

Applicant: Mohamed Shehata
Address: 204 Hill View Dr
City: Durham
State/Zip: NC 27703
Phone #: cell : (252) 425-2402

Property Owner: Anthony Clark
Address: 334 Club Pond Rd
City: Henderson
State/Zip: NC. 27537
Phone #: cell : (252) 213-7054

Property Location & Site Information

Address/Road #: Rock Mill Rd Henderson, NC 27537 Subdivision: Phase: NEW Lot:
Structure: MOBILE HOME Directions: See attachment
of Bedrooms: 3
of People: 1
*Water Supply: PUBLIC

System Specifications

*Site Classification: Provisionally Suitable Minimum Trench Depth: Inches
Design Flow: 360 Maximum Trench Depth: 12 Inches
Soil Application Rate: 0.3000 Minimum Soil Cover: Inches
*System Classification/Description: TYPE III B. SYSTEM W/SINGLE EFFLUENT PUMP Maximum Soil Cover: Inches
*Proposed System: LOW PROFILE *Distribution Type: PRESSURE MANIFOLD
Nitrification Field: 1200 Sq. ft. Septic Tank: 1,000 Gallons
No. Drain Lines: 4 Pump Required: ☒ Yes ☐ No ☐ May Be Required
Total Trench Length: 400 ft. ☐ Inches O.C. Pump Tank: 1,000 Gallons
Trench Spacing: 9 - ☒ Feet O.C. Grease Trap: Gallons
Trench Width: 3 - ☐ Inches
Aggregate Depth: inches ☒ Feet Septic Tank Installer
Grade Level Required: ☐ I ☒ II ☐ III ☐ IV

The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements.

*Permit Conditions:

LOW PROFILE CHAMBER SYSTEM. PUMP TO PRESSURE MANIFOLD. APPROVED COVER OVER ENTIRE DRAINFIELD, 6 INCHES, SLOPED TO DRAIN EXTENDING 5' BEYOND DRAINFIELD. 51' MINIMUM FROM POND.

The Authorization for Wastewater System Construction shall be valid for a period equal to the period of validity of the Improvement Permit and may be issued at the same time the Improvement Permit issued (NCGS 130A-336(b)). If the installation has not been completed during the period of validity of the Construction Permit, the information submitted in the application for a permit or Construction Authorization shall become invalid, and may be suspended or revoked (.1937(g)). The person owning or controlling the system shall be responsible for assuring compliance with the laws, rules, and permit conditions regarding system location, installation, operation, maintenance, monitoring, reporting


Authorized State Agent: Hedrick, Chris

Date of Issue: 01/31/2023

☐ Hand Drawing ☐ Import Drawing

Site Plan/Drawing attached.

Total Time : (HH:MM)



IMPROVEMENT PERMIT

Vance County Health Dept
Environmental Health
115 Charles Rollins Road
Henderson, NC 27536
Phone: (252) 492-5263 Fax: (252) 492-2361

For Office Use Only

*CDP File Number 383838 - 1
County ID Number: 0536 03043
Evaluated For: NEW

PERMIT VALID UNTIL: 01/31/2028

***NOTE TO INSPECTIONS DIVISION:** Building Permits cannot be issued with this Improvement Permit.

Applicant: Mohamed Shehata
Address: 204 Hill View Dr
City: Durham
State/Zip: NC 27703
Phone #: cell :(252) 425-2402

Property Owner: Anthony Clark
Address: 334 Club Pond Rd
City: Henderson
State/Zip: NC. 27537
Phone #: cell :(252) 213-7054

Property Location & Site Information

Address: Rock Mill Rd Henderson, NC 27537 Subdivision: Block/Phase: NEW Lot:
Road #: Directions
Structure: MOBILE HOME See attachment
of Bedrooms: 3
of People: 1
*Water Supply: PUBLIC

System Specifications

Initial System

*Site Classification: Provisionally Suitable
Design Flow: 360
Soil Application Rate: 0.3000

*System Classification/Description:
TYPE III B. SYSTEM W/SINGLE EFFLUENT PUMP

*Proposed System:
LOW PROFILE

Minimum Trench Depth: Inches
Maximum Trench Depth: 12 Inches

Septic Tank: 1000 Gallons
Pump Required ☒ Yes ☐ No ☐ May Be Required
Pump Tank: 1000 Gallons

Repair System Required: ☒ Yes ☐ No ☐ No, but has Available Space

Repair System

*Site Classification: Provisionally Suitable
Soil Application Rate: 0.300

*System Classification/Description:
TYPE III B. SYSTEM W/SINGLE EFFLUENT PUMP

*Proposed System:
LOW PROFILE

Minimum Trench Depth: Inches
Maximum Trench Depth: 12 Inches

Pump Required: ☒ Yes ☐ No ☐ May Be Required
Pump Tank: Gallons

No grading or construction activity is allowed in areas designated for system and repair without approval of Health Department

*Site Modifications

The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements.

*Permit Conditions

LOW PROFILE CHAMBER SYSTEM. PUMP TO PRESSURE MANIFOLD. APPROVED COVER OVER ENTIRE DRAINFIELD, 6 INCHES, SLOPED TO DRAIN EXTENDING 5' BEYOND DRAINFIELD. 51' MINIMUM FROM POND.

Granville-Vance Dist. Health Department
Environmental Health

Pip: _____

☒ Improvement Permit

Permit Number 383838

☒ Construction Authorization

**SITE SKETCH
ON-SITE / WELL**

Mohamed Shukita
Applicants Name

Lodi Mill Rd
Address

[Signature]
Authorized State Agent

Subdivision - Section - Lot _____

1/21/2023
Date

System components represent approximate contours only. The contractor must flag the system prior to beginning the installation to ensure that proper grade is maintained.

Area for septic repair
must be found at present
stage of building materials
or damaging during construction

