






Construction Authorization

Franklin County Health Department
107 Industrial Drive
Louisburg, NC 27549
Phone: _____

For Office Use Only

*CDP File Number: 417881 - 1
County ID Number: _____
Evaluated For: NEW

PERMIT VALID UNTIL: 09/16/2029

☐ Open Pump System Sheet

Applicant: Brandon Bailey
Address: 91 Husketh Rd
City: Youngsville
State/Zip: NC 27596
Phone #: _____

Property Owner: JSW Partners
Address: 115 Purslane Rd
City: Franklinton
State/Zip: NC 27549
Phone #: _____

Property Location & Site Information

Address/Road #: 115 Purslane Dr Franklinton, Subdivision: Woodland Park Phase: NEW Lot: 137
NC 27525
Directions:
Structure: SINGLE FAMILY 115 Purslane Dr
of Bedrooms: 3
of People: 3
*Water Supply: _____

System Specifications

Usable Soil Depth: 36 Minimum Trench Depth: _____ Inches
Design Flow: 360 Maximum Trench Depth: 24 Inches
Soil Application Rate: 0.3000
*System Classification/Description: Minimum Soil Cover: _____ Inches
TYPE II A. CONV SYSTEM (SINGLE-FAMILY OR 480 GPD OR LESS) Maximum Soil Cover: _____ Inches
*Proposed System: 25% REDUCTION *Distribution Type: PUMP TO GRAVITY
Nitrification Field: _____ Sq. ft. Septic Tank: 1,000 Gallons
No. Drain Lines: 5 Pump Required: ☒ Yes ☐ No ☐ May Be Required
Total Trench Length: 300 ft. ☐ Inches O.C. Pump Tank: 1,000 Gallons
Trench Spacing: _____ - 9 ☒ Feet O.C. Grease Trap: _____ Gallons
Trench Width: _____ - 3 ☒ Inches Septic Tank Installer: ☐ I ☐ II ☐ III ☐ IV
Aggregate Depth: _____ inches Grade Level Required: _____

The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements.

*Permit Conditions:

If builder/installer would like a deeper trench than 24 inches, EHS can visit to see tank hole when dug. This lot was fully wooded at evaluation and there were rocks and roots which made borings difficulty. There is space for a pool. System can be moved closer to home is no pool is desired, or that can become the future repair area.

There is most likely a power line easement on this lot, which may only allow 60 ft lines, if 75 ft can fit, than EHS allows 4 lines at 75 ft each.

The Authorization for Wastewater System Construction shall be valid for a period equal to the period of validity of the Improvement Permit and may be issued at the same time the Improvement Permit issued (NCGS 130A-336(b)). If the installation has not been completed during the period of validity of the Construction Permit, the information submitted in the application for a permit or Construction Authorization shall become invalid, and may be suspended or revoked (.0204(k)(1)). The person owning or controlling the system shall be responsible for assuring compliance with the laws, rules, and permit conditions regarding system location, installation, operation, maintenance, monitoring, reporting and repair (per rule .0301(a)).

Authorized State Agent: Jones, Lori Date of Issue: 09/16/2024



Hand Drawing



Import Drawing

Site Plan/Drawing attached.

Total Time : (HH:MM) _____