



IMPROVEMENT PERMIT

Franklin County Health Department
107 Industrial Drive
Louisburg, NC 27549
Phone:

For Office Use Only

*CDP File Number 449429 - 1
County ID Number:
Evaluated For: NEW

PERMIT VALID UNTIL: 03/10/2030

***NOTE TO INSPECTIONS DIVISION:** Building Permits cannot be issued with this Improvement Permit.

Applicant: Jason Ammerman
Address: 101 Cimarron
City: Louisburg
State/Zip: NC 27549
Phone #:

Property Owner: Frederick T King
Address: 216 Newport Dr
City: Jacksonville
State/Zip: NC. 28540
Phone #:

Property Location & Site Information

Address: 117 Tishomingo Drive Louisburg, NC 27549 Subdivision: Lake Royale Block/Phase: NEW Lot: 484C
Road #: **Directions**
Structure: SINGLE FAMILY 117 Tishomingo Dr
of Bedrooms: 2
of People: 2
*Water Supply: N/A

System Specifications

Initial System

Usable Soil Depth: 42

Design Flow: 240

Soil Application Rate: 0.4000

Minimum Trench Depth: Inches

Maximum Trench Depth: 30 Inches

*System Classification/Description:

TYPE III G. OTHER NON-CONV. TRENCH SYSTEMS

Septic Tank: 1000 Gallons

Pump Required ☐ Yes ☒ No ☐ May Be Required

*Proposed System:
25% REDUCTION

Pump Tank: Gallons

Repair System Required: ☐ Yes ☒ No ☐ No, but has Available Space * 15A NCAC 18A. 1945 * Repair Area Exempt

No grading or construction activity is allowed in areas designated for system and repair without approval of Health Department.

*Site Modifications

The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements.

*Permit Conditions

INSTALL ON CONTOUR. MAINTAIN PROPER SETBACKS.

The Department and Local Health Department may impose conditions on the issuance and may revoke the permits for failure of the system to satisfy the conditions, the rules, or this article. This permit is subject to revocation if the site plan, plat, or intended use changes (NCGS 130A-335(f)). The person owning or controlling the system location, installing, operation, maintenance, monitoring, reporting, and repair (per rule .0301(fa)).

Authorized State Agent: Ennis, Crystal Date of Issue: 03/10/2025

Total Time: (HH:MM)

☐ Hand Drawing

☐ Import Drawing

****Site Plan/Drawing attached.****



Construction Authorization

Franklin County Health Department
107 Industrial Drive
Louisburg, NC 27549
Phone: _____

For Office Use Only

*CDP File Number: 449429 - 1
County ID Number: _____
Evaluated For: NEW

PERMIT VALID UNTIL: 03/10/2030

☐ Open Pump System Sheet

Applicant: Jason Ammerman
Address: 101 Cimarron
City: Louisburg
State/Zip: NC 27549
Phone #: _____

Property Owner: Frederick T King
Address: 216 Newport Dr.
City: Jacksonville
State/Zip: NC. 28540
Phone #: _____

Property Location & Site Information

Address/Road #: 117 Tishomingo Drive Subdivision: Lake Royale Phase: NEW Lot: 484C
Louisburg, NC 27549
Directions:
Structure: SINGLE FAMILY 117 Tishomingo Dr
of Bedrooms: 2
of People: 2
*Water Supply: PUBLIC

System Specifications

Usable Soil Depth: 42 Minimum Trench Depth: _____ Inches
Design Flow: 240 Maximum Trench Depth: 30 Inches
Soil Application Rate: 0.4000 Minimum Soil Cover: _____ Inches
*System Classification/Description: TYPE III G. OTHER NON-CONV. TRENCH SYSTEMS Maximum Soil Cover: _____ Inches
*Proposed System: 25% REDUCTION *Distribution Type: GRAVITY - SERIAL
Nitrification Field: _____ Sq. ft. Septic Tank: 1,000 Gallons
No. Drain Lines: 4 Pump Required: ☐ Yes ☒ No ☐ May Be Required
Total Trench Length: 150 ft. ☐ Inches O.C. Pump Tank: _____ Gallons
☒ Feet O.C. Grease Trap: _____ Gallons
Trench Spacing: _____ - 9 ☐ Inches
Trench Width: _____ - 3 ☒ Feet
Aggregate Depth: _____ inches Septic Tank Installer Grade Level Required: ☐ I ☐ II ☐ III ☐ IV

The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements.

*Permit Conditions:

INSTALL ON CONTOUR. MAINTAIN PROPER SETBACKS.

The Authorization for Wastewater System Construction shall be valid for a period equal to the period of validity of the Improvement Permit and may be issued at the same time the Improvement Permit issued (NCGS 130A-336(b)). If the installation has not been completed during the period of validity of the Construction Permit, the information submitted in the application for a permit or Construction Authorization shall become invalid, and may be suspended or revoked (.0204(k)(1)). The person owning or controlling the system shall be responsible for assuring compliance with the laws, rules, and permit conditions regarding system location, installation, operation, maintenance, monitoring, reporting and repair (per rule .0301(a)).

Authorized State Agent: Ennis, Crystal Date of Issue: 03/10/2025

****Site Plan/Drawing attached.****

Total Time : (HH:MM) _____

☐ Hand Drawing ☐ Import Drawing

File# 449429PIN# 2831-34-2995Property Address: 117 Tishomingo Dr.Applicant Or Owner Name: Jason Ammerman**Environmental Health Septic/Well Permit Diagram**

Building permits cannot be issued nor should construction begin without Construction Authorization issuance.

☒ Septic Improvement Permit ☒ Septic Construction Authorization (CA) ☐ CA Reissue** ☐ As Built
☐ Well Construction Authorization ☐ Additional Diagram/Specifications Attached

Diagram Date**: 3-7-25EHS: Crystal Egan****Any previously dated CA diagram is revoked and/or invalid. Confirm this is the valid diagram for the site before beginning any construction.**Installation inspections may be scheduled the day before or the day of installation by 9am. Contact the Environmental Health office at 919 496-8100. A revisit fee may apply if installation is not ready for inspection at the time requested.SEPTIC OPERATIONS PERMITS will be issued after installation is approved, all permit conditions are met, and any outstanding fees are paid. WELL CERTIFICATE OF COMPLETION will be issued after well head approval, all permit conditions are met, and any outstanding fees are paid.Septic Tank 1000 Pump Tank / Drain field 3'x150' Type System Acc Max trench depth 30"

Septic Contractor _____ Septic/Pump tank dates _____ PUMP FEE PAID _____

Well Contractor _____ Well Head Date: _____ PUMP FINAL: _____ N/A (CIRCLE)

* Drawing not to scale *
* Layout may vary slightly *

