



OPERATION PERMIT

Franklin County Health Department
107 Industrial Drive
Louisburg, NC 27549
Phone:

For Office Use Only

*CDP File Number 448398 - 1
County ID Number: _____
Evaluated For: NEW

Applicant: Brandon Bailey

Property Owner:

Owner Address:

City:

State/Zip: /

Phone #:

Address: 125 Purslane Dr
Franklinton, NC 27525

Road #:

Township:

Subdivision: Woodland Park

Phase: NEW Lot: 136

Structure: SINGLE FAMILY

of Bedrooms: 3

of People: 3

Water Supply: NEW WELL

Saprolite System?: ☐ Yes ☒ No

Pump Required?: ☐ Yes ☒ No

Design Flow: 360

System Classification/Description: TYPE III G, OTHER
NON-CONV. TRENCH SYSTEMS

Installer: DB & SONS

Certification #: 1036

Specific System POLYSTYRENE AGGREGATE

Installed:

Septic Tank Date: 03/07/2025

STB: 502

Pump Tank Date: _____

PT:

Comments: 300' EZ FLOW INSTALLED

This system has been installed in compliance with applicable NC General Statutes, Rules for Sewage Treatment and Disposal, and all conditions of the Improvement Permit and Construction Authorization.

PERMIT CONDITIONS:

I. Performance: System shall perform in accordance with Rule .1301.

II. Monitoring: As required by Rule .1301.

III. Maintenance: Ground absorption sewage treatment and disposal systems shall be checked, and the contents of the septic tank removed, periodically from all compartments, to ensure proper operation of the system. The contents shall be pumped whenever the solids level is found to be more than 1/3 of the liquid depth in any compartment.

Other:

Subsurface Operator Required: ☐ Yes ☒ No

If yes, see attached sheet for additional operation conditions, maintenance and reporting.

Operation:

Other: 300' EZ FLOW INSTALLED

Authorized State Agent: Ennis, Crystal

Date of Issue: 04/17/2025

Owner/Applicant: _____



Lot 136

File# 448398

PIN# _____

Property Address: 125 Purslane Dr

Applicant Or Owner Name: Brandon Bailey

Environmental Health Septic/Well Permit Diagram

Building permits cannot be issued nor should construction begin without Construction Authorization issuance.

☒ Septic Improvement Permit ☒ Septic Construction Authorization (CA) ☐ CA Reissue** ☒ As Built
☒ Well Construction Authorization ☐ Additional Diagram/Specifications Attached

Diagram Date**: 2-4-2005 EHS: Joni Jones

**Any previously dated CA diagram is revoked and/or invalid. Confirm this is the valid diagram for the site before beginning any construction.

Installation inspections may be scheduled the day before or the day of installation by 9am. Contact the Environmental Health office at 919 496-8100. A revisit fee may apply if installation is not ready for inspection at the time requested. SEPTIC OPERATIONS PERMITS will be issued after installation is approved, all permit conditions are met, and any outstanding fees are paid. WELL CERTIFICATE OF COMPLETION will be issued after well head approval, all permit conditions are met, and any outstanding fees are paid.

Septic Tank 1000 Pump Tank no Drain field 3'x300' Type System Grav/Diox Max trench depth 30"
Septic Contractor DB & Sons Septic/Pump tank dates 3-7-25 5-13-02 PUMP FEE PAID _____

Well Contractor _____ Well Head Date: _____ PUMP FINAL: _____ N/A (CIRCLE)

Bedrooms: 3

If Repair: na

Acreage: .93

Parcel ID: 051028

*Drawing not to scale (if large acreage, may be portion)

(If not as built, indicate changes on front or back of sheet.)

