



Well Construction Permit

Franklin County Health Department
107 Industrial Drive
Louisburg NC, 27549
Phone: _____

For Office Use Only

*CDP File Number 449107

PIN Number: _____

Tax Lot #: _____ Tax Block #: 050886

Evaluated For: SINGLE FAMILY \ WELL

PERMIT VALID UNTIL: 03/05/2030

Property Owner: Ken Harvey Homes LLC
Address: 4909 Unicon Drive Suite 107
City: Wake Forest
State/Zip: NC / 27587
Phone #: _____

Applicant: Lisa Ferguson
Address: 4909 Unicon Drive Suite 107
City: Wake Forest
State/Zip: NC / 27587
Phone #: _____

Property Location & Site Information

Address/Road #: _____ Subdivision: _____ Phase: _____ Lot: _____
110 Broadleaf lane
Louisburg NC, 27549
*Proposed use of Well: SINGLE FAMILY
If Other: _____
Applicant Email: _____
Owner Email: _____

Directions: 110 Broadleaf Lane

Well Contractor Information

Drilling Contractor: _____ Driller Registration: _____

Permit Conditions

*Permit Conditions

Please install well according to CCSC design. Respect all setbacks.

Well location, construction and protection must meet all state and local regulations and must be inspected and approved by an authorized representative of the Local Health Department. The permit may be revoked at any time for failure to comply with existing regulations. The siting of approved well construction area(s) by the Health Department is to provide protection from the known possible sources of contamination. The approved well area(s) may not be changed without permission from an authorized representative of the Local Health Department. Issuance of this well permit does not guarantee water quality or adequate water production from the well once it is installed or repaired.

*Issued By: Jones, Lori
Authorized State Agent: _____
Owner/Applicant: _____

*Date of Issue: 03/05/2025

☐ Hand Drawing ☒ Import Drawing

****Site Plan/Drawing attached.****



Well Construction Permit

Franklin County Health Department
107 Industrial Drive
Louisburg NC, 27549
Phone:

For Office Use Only


*CDP File Number 449107

PIN Number: _____

Tax Lot #: _____ Tax Block #: 050886

Evaluated For: SINGLE FAMILY \ WELL

PERMIT VALID UNTIL: 03/05/2030



IMPROVEMENT PERMIT

Franklin County Health Department
107 Industrial Drive
Louisburg, NC 27549
Phone: _____

For Office Use Only

*CDP File Number: 449107 - 1
County ID Number: _____
Evaluated For: NEW

PERMIT VALID UNTIL: 03/05/2030

***NOTE TO INSPECTIONS DIVISION:** Building Permits cannot be issued with this Improvement Permit.

Applicant: Lisa Ferguson
Address: 4909 Unicon Drive Suite 107
City: Wake Forest
State/Zip: NC 27587
Phone #: _____

Property Owner: Ken Harvey Homes LLC
Address: 4909 Unicon Drive Suite 107
City: Wake Forest
State/Zip: NC. 27587
Phone #: _____

Property Location & Site Information

Address: 110 Broadleaf lane Louisburg, NC 27549 Subdivision: _____ Block/Phase: NEW Lot: _____

Directions

Road #: _____ 110 Broadleaf Lane

Structure: SINGLE FAMILY

of Bedrooms: 4

of People: 6

*Water Supply: N/A

System Specifications

Initial System

Usable Soil Depth: 28

Design Flow: 480

Soil Application Rate: 0.2750

Minimum Trench Depth: _____ Inches

Maximum Trench Depth: 16 Inches

*System Classification/Description:

TYPE II A. CONV SYSTEM (SINGLE-FAMILY OR 480 GPD OR LESS)

Septic Tank: 1000 Gallons
Pump Required ☒ Yes ☐ No ☐ May Be Required

*Proposed System:
25% REDUCTION

Pump Tank: 1000 Gallons

Repair System Required: ☒ Yes ☐ No ☐ No, but has Available Space

Repair System

Usable Soil Depth: 26

Soil Application Rate: 0.300

*System Classification/Description:

TYPE II A. CONV SYSTEM (SINGLE-FAMILY OR 480 GPD OR LESS)

*Proposed System: 25% REDUCTION

Minimum Trench Depth: _____ Inches

Maximum Trench: Depth: 14 Inches

Pump Required: ☒ Yes ☐ No ☐ May Be Required

Pump Tank: _____ Gallons

No grading or construction activity is allowed in areas designated for system and repair without approval of Health Department.

*Site Modifications

The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements.

*Permit Conditions

Please install septic and well in accordance with attached design sheets from CCSC. 2 inches of cover required on initial install.

CDP File Number: 449107

County ID Number:

The Department and Local Health Department may impose conditions on the issuance and may revoke the permits for failure of the system to satisfy the conditions, the rules, or this article. This permit is subject to revocation if the site plan, plat, or intended use changes (NCGS 130A-335(f)). The person owning or controlling the system location, installing, operation, maintenance, monitoring, reporting, and repair (per rule .0301((a)).

Authorized State Agent:

Jones, Lori

Date of Issue:

03/05/2025

☐ Hand Drawing

☒ Import Drawing

****Site Plan/Drawing attached.****

Total Time: (HH:MM)

____ : ____



Construction Authorization

Franklin County Health Department
107 Industrial Drive
Louisburg, NC 27549
Phone: _____

For Office Use Only

*CDP File Number: 449107 - 1
County ID Number: _____
Evaluated For: NEW

PERMIT VALID UNTIL: 02/26/2030

☐ Open Pump System Sheet

Applicant: Lisa Ferguson
Address: 4909 Unicon Drive Suite 107
City: Wake Forest
State/Zip: NC 27587
Phone #: _____

Property Owner: Ken Harvey Homes LLC
Address: 4909 Unicon Drive Suite 107
City: Wake Forest
State/Zip: NC. 27587
Phone #: _____

Property Location & Site Information

Address/Road #: 110 Broadleaf lane Louisburg, Subdivision: _____ Phase: NEW Lot: _____
NC 27549
Structure: SINGLE FAMILY 110 Broadleaf Lane
of Bedrooms: 4
of People: 6
*Water Supply: NEW WELL

System Specifications

Usable Soil Depth: 28 Minimum Trench Depth: _____ Inches
Design Flow: 480 Maximum Trench Depth: 16 Inches
Soil Application Rate: 0.2750 Minimum Soil Cover: _____ Inches
*System Classification/Description: TYPE II A. CONV SYSTEM (SINGLE-FAMILY OR 480 GPD OR LESS) Maximum Soil Cover: _____ Inches
*Proposed System: 25% REDUCTION *Distribution Type: PRESSURE MANIFOLD
Nitrification Field: _____ Sq. ft. Septic Tank: 1,000 Gallons
No. Drain Lines: 5 Pump Required: ☒ Yes ☐ No ☐ May Be Required
Total Trench Length: 460 ft. ☐ Inches O.C. Pump Tank: 1,000 Gallons
Trench Spacing: _____ - 9 ☒ Feet O.C. Grease Trap: _____ Gallons
Trench Width: _____ - 3 ☐ Inches
Aggregate Depth: _____ inches ☒ Feet Septic Tank Installer
Grade Level Required: ☐ I ☐ II ☐ III ☐ IV

The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements.

*Permit Conditions:

Please install septic in accordance with provided design by CCSC. Respect all setbacks. TAP CHARTS NEED TO BE PROVIDED BY CCSC. The builder should have a copy to provide the installer, and a copy should be uploaded to the portal.

COVER required.

The Authorization for Wastewater System Construction shall be valid for a period equal to the period of validity of the Improvement Permit and may be issued at the same time the Improvement Permit issued (NCGS 130A-336(b)). If the installation has not been completed during the period of validity of the Construction Permit, the information submitted in the application for a permit or Construction Authorization shall become invalid, and may be suspended or revoked (.0204(k)(1)). The person owning or controlling the system shall be responsible for assuring compliance with the laws, rules, and permit conditions regarding system location, installation, operation, maintenance, monitoring, reporting and repair (per rule .0301((a))).

Authorized State Agent: Jones, Lori Date of Issue: 03/05/2025

☐ Hand Drawing

☒ Import Drawing

****Site Plan/Drawing attached.****

Total Time : (HH:MM) _____

Feb 27

Lot 32



File # 449107 Parcel ID: 050886
PIN# _____

Property Address: 110 Broadleaf Ln

Applicant or Owner Name: Lisa Ferguson

Environmental Health Septic/Well Permit Diagram

Building permits cannot be issued nor should construction begin without Construction Authorization issuance.

☒ Septic Improvement Permit ☒ Septic Construction Authorization (CA) ☐ CA Reissue** ☐ As Built
☒ Well Construction Authorization ☐ Additional Diagram/Specifications Attached

Diagram Date**: 2-26-25 EHS: Rou Jones

**Any previously dated CA diagram is revoked and/or invalid. Confirm this is the valid diagram for the site before beginning any construction.

Installation/grouting inspections may be scheduled the day before, or, the day of installation until 9am by contacting the Environmental Health office at 919 496 8100. A revisit fee may apply if installation is not ready for inspection at the time requested. Septic Operations Permits will be issued after installation is approved, all permits conditions are met, and any outstanding fees are paid. Well Certificate of Completion will be issued after well head approval, all permit conditions are met, and any outstanding fees are paid.

Septic Tank 1000 Pump Tank 1000 Drainfield 3' x 40' Type System Pump to Serial Max Trench Depth 16"

Septic Contractor _____ Septic/Pump tank dates _____ Pump fee? NO YES pd _____

Well Contractor _____ Well Grout date: _____

Bedrooms: 4

*Drawing submitted by Soil Scientist

2 in
cover
2.75
LTAR

Please install septic system ^{+well} in accordance with attached design sheet(s) submitted by CCSC. Respect all setbacks.

> Enclosures / Attachments

* Cover required

Grandiflora lot 32
Initial System TAP CHART

Bench Mark:		is = 100.00		Location of BM:		Elevation Head:		16.40	
Pump tank elev.		13	87.00	Pump elev.		81.60	Manifold elevation:		98.00
line	color	rod read	Elevation	length	hole size	flow/tap	gal/day	trench area	LINE LTAR
1	White	3.00	97.00	50	1/2in SCH 80	5.48	58.08	150	0.3872
2	Orange	3.40	96.60	80	1/2in SCH 40	7.11	75.35	240	0.3140
3	Yellow	3.80	96.20	90	3/4in SCH 80	10.1	107.04	270	0.3965
4	Blue	4.20	95.80	110	3/4in SCH 80	10.1	107.04	330	0.3244
5	Purple	4.60	95.40	130	3/4in SCH 40	12.5	132.48	390	0.3397

total		feet =	460	gal/min =	45.29	LTAR =	0.2750
						LTAR + %5	0.2888
% of Dose Volume		75	Des. Flow	480		(ltar W/ INOV)	0.3667
Dose Volume		224.25	Pump Run=	10.60		(ltar W/ INOV + 5%)	0.3850
Dose Pump Time		4.95	Tank Gal/IN	19.65			
Drawdown in Inches		11.41					

Grandiflora lot 32
T&J Panel Block Repair System, TAP CHART

Bench Mark:		is = 100.00		Location of BM:		Elevation Head:		14.40				
Pump tank elev.		13	87.00	Pump elev.		81.60	Manifold elevation:		96.00			
line	color	rod read	Elevation	length	hole size	flow/tap	gal/day	trench area	LINE LTAR	# of Panels	Spacing of Panels (in)	Feet of 1.5in PVC
6	Red	5.00	95.00	87	3/4in SCH 80	10.1	129.59	261	0.4965	20	5.9	76
7	Pink	5.40	94.60	87	3/4in SCH 80	10.1	129.59	261	0.4965	20	5.9	76
8	White	5.50	94.50	85	3/4in SCH 80	10.1	129.59	255	0.5082	20	4.8	76
9	Blue	6.00	94.00	60	1/2in SCH 40	7.11	91.23	180	0.5068	14	5.1	52

				Total Number of Panels:		74
total feet =		319	gal/min =	37.41	T&J Panel Block Orientation:	Horizontal
				LTAR =	0.3000	
% of Dose Vol.	0	<u>Des. Flow</u>	480	<u>LTAR + %5</u>	0.3150	
Dose Volume	266.40	<u>Pump Run=</u>	12.83	(ltar W/ INOV)	0.6000	
Dose Pump Time	7.12	<u>Tank Gal/IN</u>	19.65	(ltar W/ INOV + 5%)	0.6300	
Drawdown in Inches	13.56					
Backfill Sand Needed:				54.3 tons	Total Footage of 1.5in PVC:	280
backfill sand needed +5%:				57.02 tons		

Grandiflora lot 32 Initial System TAP CHART

Bench Mark:		is = 100.00		Location of BM:		Elevation Head:		16.40	
Pump tank elev.		13	87.00	Pump elev.		81.60	Manifold elevation:		98.00
line	color	rod read	Elevation	length	hole size	flow/tap	gal/day	trench area	LINE LTAR
1	White	3.00	97.00	50	1/2in SCH 80	5.48	58.08	150	0.3872
2	Orange	3.40	96.60	80	1/2in SCH 40	7.11	75.35	240	0.3140
3	Yellow	3.80	96.20	90	3/4in SCH 80	10.1	107.04	270	0.3965
4	Blue	4.20	95.80	110	3/4in SCH 80	10.1	107.04	330	0.3244
5	Purple	4.60	95.40	130	3/4in SCH 40	12.5	132.48	390	0.3397

	total	feet =	460	gal/min =	45.29	LTAR =	0.2750
						LTAR + %5	0.2888
% of Dose Volume	75	Des. Flow	480			(ltar W/ INOV)	0.3667
Dose Volume	224.25	Pump Run=	10.60			(ltar W/ INOV + 5%)	0.3850
Dose Pump Time	4.95	Tank Gal/IN	19.65				
Drawdown in Inches	11.41						

Grandiflora lot 32 T&J Panel Block Repair System, TAP CHART

Bench Mark:		is = 100.00		Location of BM:		Elevation Head:		14.40				
Pump tank elev.		13	87.00	Pump elev.		81.60	Manifold elevation:		96.00	Spacing of	Feet of	
line	color	rod read	Elevation	length	hole size	flow/tap	gal/day	trench area	LINE LTAR	# of Panels	Panels (in)	1.5in PVC
6	Red	5.00	95.00	87	3/4in SCH 80	10.1	129.59	261	0.4965	20	5.9	76
7	Pink	5.40	94.60	87	3/4in SCH 80	10.1	129.59	261	0.4965	20	5.9	76
8	White	5.50	94.50	85	3/4in SCH 80	10.1	129.59	255	0.5082	20	4.8	76
9	Blue	6.00	94.00	60	1/2in SCH 40	7.11	91.23	180	0.5068	14	5.1	52

	total feet =	319	gal/min =	37.41	Total Number of Panels:		74
					T&J Panel Block Orientation:		Horizontal
					LTAR =		0.3000
% of Dose Vol.	0	Des. Flow	480		LTAR + %5		0.3150
Dose Volume	266.40	Pump Run=	12.83		(ltar W/ INOV)		0.6000
Dose Pump Time	7.12	Tank Gal/IN	19.65		(ltar W/ INOV + 5%)		0.6300
Drawdown in Inches	13.56						
		Backfill Sand Needed:		54.3 tons	Total Footage of 1.5in PVC:		280
		backfill sand needed +5%:		57.02 tons			