



OPERATION PERMIT

Franklin County Health Department
107 Industrial Drive
Louisburg, NC 27549
Phone:

For Office Use Only

*CDP File Number 394220 - 1
County ID Number: _____
Evaluated For: NEW

Applicant: Mihir Patel

Property Owner: MICHAELA A JONES
Owner Address: 3904 JONESVILLE RD

City: WAKE FOREST
State/Zip: NC/ 27549
Phone #: _____
Address: 167 OSWEGO DR
LOUISBURG, NC 27549

Road #: _____
Township: _____
Subdivision: _____
Phase : NEW Lot: _____

Structure: SINGLE FAMILY
of Bedrooms: 3
of People: 3
Water Supply: PUBLIC
Saprolite System?: ☐ Yes ☒ No
Pump Required?: ☐ Yes ☒ No
Design Flow: 360
System Classification/Description: TYPE III B. SYSTEM
W/SINGLE EFFLUENT PUMP

Installer: DB & Sons

Certification #: 1036

Specific System POLYSTYRENE AGGREGATE

Installed:

Septic Tank Date: 12/08/2023

STB:

Pump Tank Date: 01/07/2024

PT:

Comments: 300' EZ FLOW INSTALLED

This system has been installed in compliance with applicable NC General Statutes, Rules for Sewage Treatment and Disposal, and all conditions of the Improvement Permit and Construction Authorization.

PERMIT CONDITIONS:

I. Performance: System shall perform in accordance with Rule .1301.

II. Monitoring: As required by Rule .1301.

III. Maintenance: Ground absorption sewage treatment and disposal systems shall be checked, and the contents of the septic tank removed, periodically from all compartments, to ensure proper operation of the system. The contents shall be pumped whenever the solids level is found to be more than 1/3 of the liquid depth in any compartment.

Other:

Subsurface Operator Required: ☐ Yes ☒ No

If yes, see attached sheet for additional operation conditions, maintenance and reporting.

Operation:

Other: 300' EZ FLOW INSTALLED

Authorized State Agent: Ennis, Crystal

Date of Issue: 04/26/2024

Owner/Applicant: _____



File # 394220 PIN# _____

Property Address: 167 Oswego Dr

Applicant or Owner Name: Mihir Patel

Environmental Health Septic/Well Permit Diagram

Building permits cannot be issued nor should construction begin without Construction Authorization issuance.

☒ Septic Improvement Permit ☒ Septic Construction Authorization (CA) ☐ CA Reissue** ☒ As Built
☐ Well Construction Authorization ☐ Additional Diagram/Specifications Attached

Diagram Date**: 9/18/23 EHS: [Signature]

revised due to plumbing
pump 4-25-24

**Any previously dated CA diagram is revoked and/or invalid. Confirm this is the valid diagram for the site before beginning any construction.

Installation/grouting inspections may be scheduled the day before, or, the day of installation until 9am by contacting the Environmental Health office at 919 496 8100. A revisit fee may apply if installation is not ready for inspection at the time requested. Septic Operations Permits will be issued after installation is approved, all permits conditions are met, and any outstanding fees are paid. Well Certificate of Completion will be issued after well head approval, all permit conditions are met, and any outstanding fees are paid.

Septic Tank 1000 Pump Tank 1000 Drainfield 3x300 Type System PTA Max Trench Depth 30"
Septic Contractor DBS Septic/Pump tank dates ST 12-8-23 DB 1000 Pump fee? Yes NO pd 4-26-24
Well Contractor _____ Well Grout date: _____ STB 502 revised to pump CRR

✓ id tanks, lines, d-box, pump,
floats, alarm
4-26-24
CRR

