

GRANVILLE-VANCE DISTRICT HEALTH DEPARTMENT IMPROVEMENT AND OPERATION PERMITS

COUNTY:	TAX NO. <u>182400 121237</u>	TYPE OF ESTABLISHMENTS		*THIS PERMIT SHALL BE ACCOMPANIED BY A LAYOUT SHOWN ON A PLAT, INCLUDING SYSTEM REQUIREMENTS. *THIS IMPROVEMENT PERMIT IS SUBJECT TO REVOCATION IF THE INTENDED USES CHANGE FROM THOSE SHOWN ON THE IMPROVEMENT PERMIT. CHANGES SHALL REQUIRE HEALTH DEPARTMENT APPROVAL.		
<u>Granville</u>	SR. NO.	RESIDENCE ☒ BUSINESS ☐ OTHER ☐	NUMBER OF BEDROOMS: <u>4</u>		NUMBER OF OCCUPANTS: <u>8 max!</u>	
APPLICANT: <u>Wynn Construction</u>		WATER SUPPLY <u>Private</u>	WELL ☒ PUBLIC ☐		OTHER ☐	
APPLICANT'S NAME & ADDRESS: <u>2550 Capital Dr Suite 105</u> <u>Creedmore, NC 27522</u>		TYPE OF WASTEWATER SYSTEM <u>FFbg</u>	INITIAL INSTALLATION <u>FFbg</u>		REPAIR <u>FFbg</u>	
PROPERTY ADDRESS/LOCATION: <u>Pittsford Circle</u>		DESIGN FLOW:	<u>480 GPD</u>		*THIS IMPROVEMENT PERMIT IS SUBJECT TO REVOCATION IF THE INTENDED USES CHANGE FROM THOSE SHOWN ON THE IMPROVEMENT PERMIT. CHANGES SHALL REQUIRE HEALTH DEPARTMENT APPROVAL.	
		LTAR:	<u>3 GRD</u>			
SUBDIVISION: <u>Chaslergh</u>		ABSORPTION AREA:	<u>1720 ft²</u>	<u>1780 ft²</u>		*THIS IMPROVEMENT PERMIT IS SUBJECT TO REVOCATION IF THE INTENDED USES CHANGE FROM THOSE SHOWN ON THE IMPROVEMENT PERMIT. CHANGES SHALL REQUIRE HEALTH DEPARTMENT APPROVAL.
LOT NUMBER: <u>123</u>		TRENCH WIDTH:	<u>3'</u>			
REFERENCE SKETCH (SEE PLAT FOR DETAILS)		TRENCH DEPTH:	<u>20"</u>		PERMIT VALID FOR: 5 YEARS ☒ YES ☐ NO	
		TRENCH SPACING:	<u>9' O.C.</u>			
		TOTAL TRENCH LENGTH:	<u>430'</u>			
		NUMBER OF TRENCHES:	<u>1 Serial</u>	<u>4</u>		
		GRAVEL DEPTH:	<u>Accepted</u>			
		TANK SIZE:	<u>1000 Gallons</u>			
		PUMP TANK SIZE:		<u>1000 Gallons</u>		
		DISTRIBUTION DEVICE:	<u>8" by</u>	<u>Pressure Main</u>	NO EXPIRATION YES ☒ NO ☐	

***** IMPROVEMENT PERMIT DATE: 8/26/16 *****

FOR: Wynn Construction
 ISSUED BY: Chris Hadd

***** CONSTRUCTION AUTHORIZATION FOR IMPROVEMENT PERMIT# 8765 *****

Unless otherwise indicated, the same conditions above apply regarding system type, layout, location and installation requirements.
 (The wastewater system cannot be installed until authorization is signed)

Comments: Install according to attached plan

Date: 8/26/16 Environmental Health Specialist: Chris Hadd
 Construction Authorization Addendum ☒ Yes ☐ No

***** OPERATION PERMIT DATE: *****


SYSTEM INSTALLED BY: _____
 ISSUED BY: _____

Chesleigh, Lot 123
4-Bedroom Septic System Layout
June 2016

System: =====
Repair: —————

Proposed New Lot Line

New Lot 123 Repair Area



Keep Tanks and Drain Lines 10' from property lines.
 Not a Survey
 Not a guarantee of a septic permit.
 Keep supply lines >5' from property lines.
 Some lines are flagged longer in the field than lengths indicated above.

System: Gravity to Serial Dist.
 Lines: 1-6, (430')
 Accepted Status System
 0.3 Soil LTAR
 20' Trench Bottom

Repair: Pressure Manifold
 Lines: 7-10, (445')
 Accepted Status System
 0.3 Soil LTAR
 20' Trench Bottom

Central Carolina
 Soil Consulting
 919-569-6704
 Project # 1852

Chesleigh, Lot 123 TAP CHART

Bench Mark	is = 100.00		Location of BM:		Elevation Head		-89.00		
Pump tank el	0	5	95.00	Pump elev.	90.00	Manifold elev.	1.00		
line	color	rod read	Elevation	length	hole size	flow/tap	gal/day	trench area	LINE LTAR

	total	feet =	0	gal/min =	0	<u>LTAR =</u>	0.3000
						<u>LTAR + %5</u>	0.3150
% of Dose Vol.	75	<u>Des. Flow</u>	480			(ltar W/ INOV)	0.4000
Dose Volume	0.00	Pump Run=	#DIV/0!			(ltar W/ INOV + 5%)	0.4200
Dose Pump Time	#DIV/0!	Tank Gal/IN	21				
Drawdown in Inches	0.00						

Chesleigh, Lot 123 Repair TAP CHART

Bench Mark		is = 100.00		Location of BM:		Elevation Head			-7.70
Pump tank elev.		5	95.00	Pump elev.	90.00	Manifold elev.			82.30
line	color	rod read	Elevation	length	hole size	flow/tap	gal/day	trench area	LINE LTAR
7	Red	18.70	81.30	140	1in SCH 80	16.8	173.38	420	0.4128
8	Blue	20.30	79.70	125	3/4in SCH 40	12.5	129.00	375	0.3440
9	Pink	22.6	77.40	100	3/4in SCH 80	10.1	104.24	300	0.3475
10	Orange	24.4	75.60	80	1/2in SCH 40	7.11	73.38	240	0.3057

	total	feet =	445	gal/min =	46.51	<u>LTAR =</u>	0.3000
						<u>LTAR + %5</u>	0.3150
% of Dose Vol.	75	<u>Des. Flow</u>	480			(ltar W/ INOV)	0.4000
Dose Volume	216.94	Pump Run=	10.32			(ltar W/ INOV + 5%)	0.4200
Dose Pump Time	4.66	Tank Gal/IN	21				
Drawdown in Inches	10.33						

Granville - Vance District Health Department

Environmental Health

1926

Well Construction Permit

Owner/Applicant: Wyna Construction Date: 8/26/16
Address or Location of Property: B. Holly Circle


Subdivision & Lot #: Cherokee 123 Septic Permit #: 8765
Zoning Permit #: 14265 Environmental Health Specialist: Chet

This well permit is to locate and site the area that a private groundwater well may be established on the property listed above by the Environmental Health Specialists of Granville County. If one does not locate the well in the approved area and complete the well as specified by the 15A NCAC .02C rules, then permits may be revoked. At completion of drilling of the well, grout must be witnessed by EHS and a well log turned into Environmental Health.

Minimum Setbacks: (these are the main setbacks, but not all required setbacks)

Setback from property lines – 10 ft Setback from septic tank and drain field, including repair area – 100 ft
Setback from structural foundations – 25 ft Setback from ponds, lakes or other bodies of water – 50 ft

Site Sketch:



Conditions: _____

Authorized Agent: Chris Heall

Date: 8/26/16

1 Well Grout: (Circle or write in)

Witnessed: Yes or No EHS Agent: _____

Date: _____ Annular Space Open: Yes or No

Over reamed: Yes or No Depth Grouted: _____


Method: _____ Pump _____ Poured _____ Pressure

Well Log received: Yes or No (EHS to Attach to Permit)

Driller Name: _____ Cert. # _____

Depth: _____ Casing Depth: _____ GPM: _____

As Built Drawing:

**# 2 Well Final: (Place a check mark when finalized)**

Seal Present and Intact: _____ Air Vent: _____

Hose Spigot: _____ Electrical Box: _____

Pump Installer Tag: _____ Well Installer Tag: _____

All holes sealed: _____ 12" above grade: _____

Comments: _____

3 Well Completion Permit: _____ **EHS**

Date Completed: _____

4 Water Samples Taken: Date: _____

EHS: _____ **Results:** _____

Retest: _____ **Results:** _____

Chesleigh, Lot 123
4-Bedroom Septic System Layout
June 2016

System: 
Repair: 

