

* Pump System

PERMIT NUMBER **3509**

GRANVILLE-VANCE DISTRICT HEALTH DEPARTMENT IMPROVEMENT AND OPERATION PERMITS

COUNTY:	TAX NO.	TYPE OF ESTABLISHMENT			*THIS PERMIT SHALL BE ACCOMPANIED BY A LAYOUT SHOWN ON A PLAT, INCLUDING SYSTEM REQUIREMENTS.
Vance	SR. NO.	RESIDENCE ☒	NUMBER OF BEDROOMS:	NUMBER OF OCCUPANTS:	
OWNER: Curtis White		BUSINESS ☐	3	≤ 6	
APPLICANT: Den Mark Constr		OTHER ☐			
APPLICANT'S ADDRESS:		WATER SUPPLY			*THE IMPROVEMENTS PERMIT MUST BE ATTACHED TO A CONSTRUCTION AUTHORIZATION BEFORE OBTAINING BUILDING PERMIT OR OTHER CONSTRUCTION PERMITS AND BEFORE A WASTEWATER SYSTEM IS INSTALLED.
		PUBLIC ☒	WELL ☐	OTHER ☐	
PROPERTY ADDRESS/LOCATION:		TYPE OF WASTEWATER SYSTEM			
131 Cobblecreek Dr.		Pump to Innovative (Two Manifolds)			
		DESCRIPTION	INITIAL INSTALLATION	REPAIR Ultra Shallow	
SUBDIVISION: Cobble Stone		DESIGN FLOW:	360 g/day	Innovative + Perimeter Drain	
LOT NUMBER: 60		LTAR:	.3		
REFERENCE SKETCH (SEE PLAT FOR DETAILS)		ABSORPTION AREA:	1,200 ft²	(900 ft² w/ innovative)	
		TRENCH WIDTH:	3'	3'	
		TRENCH SPACING:	9'	9'	
		TOTAL TRENCH LENGTH:	300'	300'	
		NUMBER OF TRENCHES:	4		
		GRAVEL DEPTH:	NA	12"	
		TANK SIZE:	1,000 g ST		
		CONDITIONS:	18" Maximum Trench Depth		
Cobble Cree Dr. IMPROVEMENT PERMIT FOR: Curtis White ISSUED BY: Mac Shingleton, R8					DATE: 1-14-03
OPERATION PERMIT SYSTEM INSTALLED BY: James Bailey ISSUED BY: Mac Shingleton, R8					DATE: 11-20-03

* Pump system final check on 11-18-03.

MAC

EZ Flow Drainfield.

