

Environmental Services - Water Quality
Onsite Wastewater Scan Data Entry Form

PERMIT #: D013908

PIN #: 0760296317

OP DATE: 0812311999

SYSTEM USE:

- ☒ House
☐ Mobile Home
☐ Business
☐ Other

SEWAGE TYPE:

- ☒ Domestic
☐ Industrial

PUMP/SIPHON?:

- ☐ Yes
☒ No

PRESSURE MANIFOLD:

- ☐ Yes
☒ No

SYSTEM TYPE:

- ☐ I
☐ II
☒ III
☐ IV
☐ V
☐ VI
☐ Other

SUB TYPE:

- ☐ A
☐ B
☐ C
☐ D
☐ E
☐ F
☒ G

NBR BEDROOMS:

- ☐ 1
☐ 2
☐ 3
☒ 4
☐ 5
☐ 6
☐ Other

MAINT. SCHEDULE:

- ☐ Yes
☒ No

CERT. OPERATOR

- ☐ Yes
☒ No

GT ST PT SIZE

DRAINFIELD SIZE(SQ. FT.)

01500

DRAIN TYPE:

- ☐ 750
☐ 900
☐ 1,000
☐ 1,200
☒ 1,500
☐ 1,800
☐ 2,100
☐ 2,500
☐ 3,000
☐ 4,000
☐ 5,000
☐ 8,000
☐ 10,000
☐ Other
☒ None/NA GT or PT

- ☒ Stone
☐ EZ Flow
☐ Infiltrator
☐ Biodiffuser
☐ Cultec
☐ Drip
☐ Hancor
☐ Large Dia. Pipe
☐ Multi-Pipe
☐ Other

MAX DEPTH (IN.):

- ☐ 12 in. or less
☐ 18 in. or less
☐ 24 in. or less
☒ 26 in. or less
☐ 28 in. or less
☐ 30 in. or less
☐ 32 in. or less
☐ 36 in. or less
☐ Other

STONE DEPTH (IN.):

- ☐ 8 in. or less
☒ 12 in. or less
☐ 18 in. or less
☐ 24 in. or less
☐ Other

TRENCHES:

- ☒ Individual
☐ Bed

TRENCH WIDTH (IN.):

- ☐ 12 in. or less
☐ 18 in.
☐ 24 in.
☒ 36 in.
☐ 6 ft. or less
☐ 9 ft. or less
☐ Other

B.W 7/10/14

WAKE COUNTY DEPARTMENT OF ENVIRONMENTAL SERVICES WELL AND SEWAGE SITE LOCATION PERMIT

NO PERMIT(S) FOR CONSTRUCTION, LOCATION OR RELOCATION ACTIVITY SHALL BE ISSUED

UNTIL AN AUTHORIZATION FOR WASTEWATER SYSTEM CONSTRUCTION HAS BEEN ISSUED

PERMIT VOID IF NOT IN COMPLIANCE WITH ZONING REGULATIONS AND/OR IF SITE IS ALTERED OR INTENDED USE CHANGED

PERMIT#: D013908 STATUS: A APP DATE: 03/25/1999 BLDG PERMIT#: 0993461
 APPLICANT: YOUNG, SAM BUILDER DAY PHONE: (919) 773 - 1252
 ADDRESS: 5501 TEN TEN RD FAX#: (000) 000 - 0000
 CITY: APEX STATE: NC ZIP: 27502
 OWNER: WINSLOW PROPERTIES DAY PHONE: (919) 999 - 9999
 ADDRESS: 1011 SCHAUB DR FAX#: (000) 000 - 0000
 CITY: RALEIGH STATE: NC ZIP: 27606
 HD USE CD: 101 ONE-FAMILY HOUSE ORIG PERMIT#: REC?: Y
 EXIST USE: 5 BSMT: N #EMPLOYEES: 0 WATER: I WASTEWATER: I GARB DISPOS: N
 BEDROOMS: 5 TOWNSHIP: 18 SWIFT CREEK JURIS: WC ZON: R30 PIN: 0760.01 29 6543 000
 SUBD#: S 000 000 00 SUBD NAME: GRENADIER LOT-SEC: 13 ACRES: 0.70
 IMPRV PRMT: ISSUED?: Y DATE: 04/29/1999 BY: SES TYPE SYSTEM: III G PUMP:
 CNSTR AUTH: ISSUED?: Y DATE: 04/29/1999 BY: SES MAINT: N OPER: N
 RECEIPT#: 0040322 FEE: 290.00 OP DATE: BY:
 WATR SAMPL: REQ?: Y APPROVED?: DATE: PROPRIETARY SYS:
 ST#: 4009 MI: DIR: NAME: CHAUMONT DIR: TYP: DR
 DIRECTIONS: SR 1152 S TO R ON SR 1010 TO L INTO SUB

IMPROVEMENT PERMIT

SIZE OF TANK 1500 ST PT GALS. TOTAL SQ. FT. 1500* DEPTH OF STONE INNOV IN. MAX. DEPTH LINE 26 IN.

WASTEWATER: DOMESTIC ☒ INDUSTRIAL ☐ I.P. ISSUED BY [Signature]

AUTHORIZATION FOR WASTEWATER SYSTEM CONSTRUCTION

VOID SIXTY (60) MONTHS FROM DATE OF ISSUANCE

AUTHORIZATION CONDITIONS

Contractor To Follow Contours, See Attached Site Plan For Wastewater System Design And Well Location. The wastewater system shall not be covered or placed into use until inspected by the Wake County Department of Environmental Services and an Operation Permit issued.

OTHER CONDITIONS: SEPTIC SYSTEM INSTALLER TO KEEP ALL PARTS OF SEPTIC SYSTEM (INCLUDING SEPTIC TANK) 10 FEET AWAY FROM BUILDING FOUNDATION, *reflects actual innovative square footage with 25% reduction reflected, extremely tight fit for system between property line and house, house MUST be at least 50 feet off left side property line, note 2 drainage swales that are required, owner to elect appropriate innovative product 12" INNOV

SIZE OF TANK 1500 ST PT GALS. TOTAL SQ. FT. 1500* DEPTH OF STONE 9 IN MAX. DEPTH LINE 26 IN.

ST FILTER REQUIRED ☒ NUMBER OF TRENCHES 4 LENGTH OF TRENCHES 125* FT. WIDTH OF TRENCHES 3 FT.

C.A. ISSUED BY [Signature] INSTALLED BY [Signature] CTR. I.D. # _____

SEPTIC TANK FILTER USED _____

INNOV. APPL. #: IWWS- _____ DATE 3/23/99 INSTALLATION APPROVED BY [Signature]

WELL SYSTEM = PRIVATE ☒ SEMI-PUBLIC ☐ NEW ☒ REPLACEMENT ☐ EXISTING ☐

WELL LOG INFORMATION = DEPTH 220' CASING DEPTH 112' YIELD 8 STATIC LEVEL 20'
 WELL CONTRACTOR [Signature] REG.# 479 PUMP CONTRACTOR [Signature] REG.# 781

CONSTRUCTION COMPLIANCE = GROUT APPROVED ☒ DATE 5/6/99 EHS [Signature]

WCHD ID # _____ WELLHEAD APPROVED ☒ DATE 7/1/99 EHS [Signature]

NEGATIVE BACTERIOLOGICAL RESULTS ☒ DATE 10/29/99 EHS [Signature]

SYSTEM FINALIZED ☒ DATE 10/29/99 EHS [Signature]

COMMENTS: _____

 This permit is based in part on information provided by the homeowner or his/her representative in the application submitted for this permit. The Environmental Health Specialist is not responsible for false or misleading information contained in the application. The Environmental Health Specialist is also not responsible for concealed conditions on the property or for statements in this report that may have resulted from false or misleading statements provided to him in the application. Neither Wake County nor the Environmental Health Specialist warrants that the septic tank system will continue to function satisfactorily in the future or that the water supply will remain potable.

am Young
UILDERS, INC.

5501 Ten-Ten Road Apex, North Carolina 27502

Phone (919) 779-1417

Fax (919) 773-1253

0993461

D-13908
0009 CHAUMONT

LOT # 13 GRENADIER
4009 CHAUMONT DRIVE
30.32 SQ. FT. 0.70 AC.
SCALE: 1" = 40'

I certify that the location of planned or existing structure(s) has been accurately shown. I understand failure to locate structures in accordance with this plot plan may require the relocation of structure(s) regardless degree of completion. I hereby grant permission to Municipal/County Representatives the right of entry to make evaluations or inspections upon this property.

Drach Young

Zoning R30 By m7

Approve ✓ Date 3/25/99

Revised Use 101

Reject MBL


Front 30 Rear 30

Side 10 Corner

Comments:

THIS WILL
BE PARADE
HOUSE

KEEP ALL PARTS OF
SEPTIC SYSTEM 10
FEET AWAY FROM
BUILDING FOUNDATION.




WAKE COUNTY

Department of Environmental Services

Water, Wastewater and Development Services

(919) 856-7400 FAX: (919) 856-7407

PO Box 550, Raleigh, NC 27602

**REVISIONS THAT DO NOT NEED REVISED SITE PLANS**D # 13908Building Permit # 0993461

- Change of Bedrooms from 5
to 4
- Change of Name on Permit *
- Change of Foundation
- Change of Garbage Disposal
- Change of Employees

* Need Name, Address and Phone Number of New Applicant

Comments:

Applicant Signature [Signature] Date 7/26/99Permit Processor [Signature] Date 7/26/99**To protect and improve the quality of Wake County's environment and ensure a healthy future****for its citizens through cooperation, education, management and enforcement**JUL 27 1999
Revise

North Carolina - Department of Environment and Natural Resources - Division of Water Quality - Groundwater Section
P.O. Box 29578 - Raleigh, N.C. 27626-0578-Phone (919) 733-3221

013908

WELL CONSTRUCTION RECORD

DRILLING CONTRACTOR: Grady Poole

DRILLER REGISTRATION #: _____

STATE WELL CONSTRUCTION PERMIT#: _____

1. WELL USE (Check Applicable Box): Residential ☒ Municipal ☐ Industrial ☐ Agricultural ☐ Monitoring ☐
Recovery ☐ Heat Pump Water Injection ☐ Other ☐ If Other, List Use: _____

2. WELL LOCATION: (Show sketch of the location below)

Nearest Town: Cary County: Wake

Lot 13 Grenadier

(Road, Community, or Subdivision and Lot No.)

3. OWNER Sam Young blars.

ADDRESS 5501 Ten-Ten rd.

(Street or Route No.)

Apex NC

City or Town

State

27502

Zip Code

4. DATE DRILLED 5-18-99

5. TOTAL DEPTH 220

6. CUTTINGS COLLECTED YES ☐ NO ☒

7. DOES WELL REPLACE EXISTING WELL? YES ☐ NO ☒

8. STATIC WATER LEVEL Below Top of Casing: 20 FT.

9. TOP OF CASING IS 1 1/2 FT. Above Land Surface*
(Use "+" if Above Top of Casing)

* Casing Terminated at or below land surface is illegal unless a variance is issued in accordance with 15A NCAC 2C .0118

10. YIELD (gpm): 8 METHOD OF TEST Blow

11. WATER ZONES (depth): 170

12. CHLORINATION: Type HTH Amount 1 lb.

13. CASING:

From	Depth	To	Ft.	Diameter	Wall Thickness or Weight/Ft.	Material
0	112			6 1/4	.188	galvanized
From	To	Ft.				
From	To	Ft.				

14. GROUT:

From	Depth	To	Ft.	Material	Method
0	20			port. screen	gravity
From	To	Ft.			

15. SCREEN:

From	Depth	To	Ft.	Diameter	Slot Size	Material
From	To	Ft.				
From	To	Ft.				
From	To	Ft.				

16. SAND/GRAVEL PACK:

From	Depth	To	Ft.	Size	Material
From	To	Ft.			
From	To	Ft.			

17. REMARKS:

DEPTH

From To

0 - 2

2 - 50

50 - 112

112 - 220

DRILLING LOG

Formation Description

topsoil

clay


sand

slate rock

If additional space is needed use back of form

LOCATION SKETCH

(Show direction and distance from at least two State Roads, or other map reference points)



I DO HEREBY CERTIFY THAT THIS WELL WAS CONSTRUCTED IN ACCORDANCE WITH 15A NCAC 2C, WELL CONSTRUCTION STANDARDS, AND THAT A COPY OF THIS RECORD HAS BEEN PROVIDED TO THE WELL OWNER.

SIGNATURE OF CONTRACTOR OR AGENT

Submit original to Division of Water Quality and copy to well owner.

DATE

5-18-99

GW-1 REV. 1/98