



NC DEPARTMENT OF
**HEALTH AND
HUMAN SERVICES**

ROY COOPER • Governor
KODY H. KINSLEY • Secretary
MARK BENTON • Chief Deputy Secretary for Health
SUSAN KANSAGRA • Assistant Secretary for Public Health
Division of Public Health

Submittal Includes: ☒ (a2) Improvement Permit ☒ (a2) Construction Authorization ☐ Fee \$ _____

IMPROVEMENT PERMIT FOR G.S. 130A-335(a2)

County: Wake
PIN/Lot Identifier: 1798261134
Issued To: Rhapsody Property Group, LLC.
Property Location: 8520 Pascola Way, Zebulon
Subdivision (if applicable) Lennox Manor Lot #: 14 Block: _____ Section: _____
LSS Report Provided: Yes ☒ No ☐
If yes, name and license number of LSS: Jason Hall, NC LSS #1248
New ☒ Expansion ☐ System Relocation ☐ Change of Use ☐
Facility Type: single family
Number of bedrooms: 4 Number of Occupants: <8 Other: _____
Design Wastewater Strength: ☒ Domestic ☐ High Strength ☐ Industrial Process Wastewater
Proposed Design Daily Flow: 480 GPD Proposed LTAR (Initial): .275 Proposed LTAR (Repair): .275
Proposed Wastewater System Type*: IIIbg (Initial) Pump Required: ☒ Yes ☐ No ☐ May be required
Proposed Wastewater System Type*: IIIbg (Repair) Pump Required: ☒ Yes ☐ No ☐ May be required
**Please include system classification for proposed wastewater system types in accordance with Rule .1301 Table XXXII*
Effluent Standard: ☒ DSE ☐ HSE ☐ NSF/ANSI 40 ☐ TS-I ☐ TS-II ☐ RCW
Saprolite System (Initial): ☒ Yes ☐ No Saprolite System (Repair): ☒ Yes ☐ No
Fill System (Initial): ☐ Yes ☒ No If yes, specify: ☐ New ☐ Existing (when adding more than 6 inches of fill to system area provide a fill plan)
Fill System (Repair): ☐ Yes ☒ No If yes, specify: ☐ New ☐ Existing (when adding more than 6 inches of fill to system area provide a fill plan)
Usable Depth to LC (Initial)*: 48 Usable Depth to LC (Repair)*: 48 * **Limiting Condition**
Max. Trench Depth (Initial)*: 24 Max. Trench Depth (Repair)*: 24 * **Measured on the downhill side of the trench**
Artificial Drainage Required: ☐ Yes ☒ No If yes, please specify details: _____
Type of Water Supply: ☒ Private well ☐ Public well ☐ Shared well ☐ Municipal Supply ☐ Spring ☐ Other: _____
Drainfield location meets requirements of Rule .0508: Yes ☒ No ☐ Drainfield location meets requirements of Rule .0601: Yes ☒ No ☐
Permit valid for: ☒ Five years [site plan submitted pursuant to GS 130A-334(13a)] ☐ No expiration [plat submitted pursuant to GS 130A-334(7a)]

Permit conditions:

Rock could be encountered less than trench depth, due to local area.
Bridge over any potential rock areas with solid 3" pvc

Licensed Soil Scientist Print Name: Jason Hall

Licensed Soil Scientist Signature: [Signature] Date: 1/20/26

The LSS evaluation is being submitted pursuant to and meets the requirements of G.S. 130A-335(a2).

See attached site sketch



This Section for Local Health Department Use Only

Initial submittal received: 2/13/2026 by JLA
Date Initials

G.S. 130A-335(a3) states the following:

When an applicant for an Improvement Permit submits to a local health department an Improvement Permit application, the permit fee charged by the local health department, the common form developed by the Department, and a soil evaluation pursuant to subsection (a2) of this section, the local health department shall, within five business days of receiving the application, conduct a completeness review of the submittal. A determination of completeness means that the Improvement Permit includes all of the required components. If the local health department determines that the Improvement Permit is incomplete, the local health department shall notify the applicant of the components needed to complete the Improvement Permit. The applicant may submit additional information to the local health department to cure the deficiencies in the Improvement Permit. The local health department shall make a final determination as to whether the Improvement Permit is complete within five business days after the local health department receives the additional information from the applicant. If the local health department fails to act within any period set out in this subsection, the applicant may treat the failure to act as a determination of completeness. The Department shall develop a common form for use as the Improvement Permit.

The review for completeness of this Improvement Permit was conducted in accordance with G.S. 130A-335(a3). This Improvement Permit is determined to be:

☐ Incomplete (If box is checked, information in this section is required.)

The following items are missing:

Copies of this were sent to the LSS and the Applicant on _____
Date

State Authorized Agent: _____ Date: _____

☒ Complete

State Authorized Agent: James Adcock Date: 2/19/2026

This Improvement Permit is issued pursuant to G.S. 130A-335 (a2) and (a3) using the signed and sealed LSS/LG evaluation(s) attached here. The issuance of this permit in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This permit is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of 15A NCAC 18E and to the conditions of this permit.

The Department, the Department's authorized agents, and the local health departments shall be discharged and released from any liabilities, duties, and responsibilities imposed by statute or in common law from any claim arising out of or attributed to evaluations, submittals, or actions from a licensed soil scientist or licensed geologist pursuant to GS 130A-335(a2).

Improvement Permit Expiration Date: 2/18/2031



Public Health Onsite Water Protection

This Improvement Permit is issued pursuant to G.S. 130A-335 (a2) and (a3) using the signed and sealed LSS/LG evaluation(s) attached here. Applicant is responsible for adhering to all State and Local rules, regulations and laws.

Re-submittal of Improvement Permit

LHD USE ONLY: This IP resubmittal received: _____ by _____
Date *Initials*

The following items are being resubmitted pursuant to G.S. 130A-335(a3) for issuance of the Improvement Permit:

I, _____ hereby attest that the information required to be included with this re-submittal
Licensed Soil Scientist (Print Name)
is accurate and complete to the best of my knowledge and that the proposed Improvement Permit meets all applicable federal,
State, and local laws, regulations, rules, and ordinances.

Signature of Licensed Soil Scientist

Date

The section below is for Local Health Department use after submittal of items noted as missing above.

LHD Follow-up Completeness Review of Improvement Permit

The review for completeness of this Improvement Permit re-submittal was conducted in accordance with G.S. 130A-335(a3). This Improvement Permit is determined to be:

☐ Incomplete (If box is checked, information in this section is required.)

The following items are missing:

Copies of this were sent to the LSS and the Applicant on _____
Date

State Authorized Agent: _____

Date: _____

☐ Complete

State Authorized Agent: _____

Date: _____



Central Carolina Soil Consulting, PLLC

1900 South Main Street, Suite 110, Wake Forest, NC 27587

Office Number: 919-569-6704

January 20, 2026

Job # 5387

Rhapsody Property Group, LLC.
PO Box 1733
Fuquay Varina, NC 27526

RE: Preliminary soil/site evaluation for single family wastewater approval at lot 14 in Lennox Manor, Wake County pursuant to and meets the requirements of G.S. 130A-335(a2)."

To Whom it May Concern:

Central Carolina Soil Consulting, PLLC conducted a preliminary soil evaluation on the aforementioned lot to determine the areas of provisionally suitable soils that are suitable for subsurface wastewater disposal systems (conventional, Accepted & Innovative). **"The LSS evaluation is being submitted pursuant to and meets the requirements of G.S. 130A-335(a2)."** The soil/site evaluation was performed using auger borings in January 2026 under moist soil conditions, based on the criteria found in the State Subsurface Rules, 15A NCAC 18E "Wastewater Treatment and Dispersal Systems". From this evaluation, CCSC laid out and located the septic layout and gps'd for site plan drawing purposes. **Please note that the lot lines must be clearly marked by your surveyor prior to system installation by your installer to verify all setbacks before digging.**

The lot is proposed to have a 4-bedroom system for the house. A septic system field layout was completed based on the house location and property lines surveyed in the field.

The proposed Initial system for the house is a pressure manifold distribution using lines 1-4 totaling 460 feet of accepted status product (EZ-Flow or Chambers). The repair system for the house is a pressure manifold distribution using lines 5-8 totaling 460 feet of accepted status product (EZ-Flow or Chambers). The septic & pump tanks for the house should be minimum 1,200 gallons with risers. The septic tank should also have pressed in rubber boots on both the inlets and the outlets of the tank, along with having secondary lids on all the openings.

Based on the findings during the field evaluation, the area on the attached map has at least 48 inches (initial) and 48 inches (repair) of provisionally suitable soils/saprolite for a modified conventional septic system. The assigned LTAR for the site is 0.275 gpd/ft² with a maximum depth of 24 inches for the initial system installation of the drain lines due to slope correction. The assigned LTAR for the site is 0.275 gpd/ft² with a maximum depth of 24 inches for the repair system installation of the drain lines due to slope correction.

Septic Installation:

The septic system for the lot should be installed during dry soil conditions. The septic system should be installed on contour while maintaining all required setbacks. **Lot lines must be clearly marked by your surveyor prior to system installation so your installer can verify all setbacks before digging.**

Setbacks: (see septic design page for locations)

- **Septic and Pump Tanks** (see septic design)
 - 10' minimum from property lines
 - 5' minimum from house
- **Septic Lines** (see septic design)
 - 10' minimum from property lines
 - 5' minimum from house
- **Manifold's and D-Box's** (see septic design)
 - 10' minimum from property lines
- **Supply Lines** (see septic design)
 - 5' minimum from property lines
- **Utilities**
 - Water (10' minimum for all septic components)
 - Power, cable, internet, etc. (5' minimum setback)

Grading:

No grading should be completed within the initial and repair septic areas that change the natural grade of the area. There should be no cutting or filling within the septic areas as well. When grading the lot, no cuts of 2' or greater should be within 15' of the septic areas. If a cut is required near the septic area, keep the cut around 6-8 inches in depth.

HOUSE:

- Initial System: PM Distribution, lines 1-4 totaling 460' (see layout)
- Repair System: PM Distribution, lines 5-8 totaling 460' (see layout)
- 480 gal/day flow rate (4-bedroom)
- 1,200 gallon septic tank with risers and pressed in rubber boots on both the inlet and outlet ends and a secondary lid in each tank opening
- 24" max trench depth for Initial System
- 24" max trench depth for Repair System
- 0.275 LTAR for Initial
- 0.275 LTAR for Repair
- No grading/filling septic areas
- No cuts >2' within 15' of septic areas
- Keep tanks and drain lines 10' from property lines
- Keep supply line >5' property lines
- Install in dry soil conditions
- Maintain natural contours when clearing the lot

This letter discusses the location of provisionally suitable soils for subsurface wastewater disposal systems and does not guarantee the future function of any wastewater system on sites. Central Carolina Soil Consulting, PLLC is a professional consulting firm specializing in soil delineations and designs for on-site wastewater disposal systems.

If you have any questions regarding the findings on the attached map or in this report, please feel free to contact me at any time. Thank you for allowing Central Carolina Soil Consulting to perform this site evaluation for you.

Sincerely,




Jason Hall

NC Licensed Soil Scientist #1248

AOWE certification number 10004E

Encl: Soil Map & septic layout



Central Carolina Soil Consulting, PLLC

1900 South Main Street, Suite 110, Wake Forest, NC 27587


SOIL/SITE EVALUATION for ON-SITE WASTEWATER SYSTEM
(Complete all fields in full)

OWNER: _____ Rhapsody Property Group, LLC. DATE EVALUATED: 1-15-26
ADDRESS: _____ PO Box 1733, Fuquay Varina
PROPOSED FACILITY: 4-Bedroom PROPOSED DESIGN FLOW (.0400): 480 PROPERTY SIZE: _____
LOCATION OF SITE: 8520 Pascola Way, Zebulon PROPERTY RECORDED: yes
WATER SUPPLY: ☐ Public ☒ Single Family Well ☐ Shared Well ☐ Spring ☐ Other _____ WATER SUPPLY SETBACK: _____
EVALUATION METHOD: ☒ Auger Boring ☐ Pit ☐ Cut TYPE OF WASTEWATER: ☒ Domestic ☐ High Strength ☐ IPWW

P R O F I L E #	.0502 LANDSCAPE POSITION/ SLOPE %	HORIZON DEPTH (IN.)	SOIL MORPHOLOGY		OTHER PROFILE FACTORS				.0509 PROFILE CLASS & LTAR*	.0502(d) SLOPE CORRECTION
			.0503 TEXTURE/ STRUCTURE	.0503 CONSISTENCE/ MINERALOGY	.0504 SOIL WETNESS/ COLOR	.0505 SOIL DEPTH	.0506 SAPRO CLASS	.0507 RESTR HORIZON		
1	R-7	A, 0-6	SL, Gr	VFR, NS, NP						3"
		Bt, 6-28	Clay, SBK	FI, S, SP, SEXP		S			S.275	
		BC, 28-38	CL, Wk SBK	FI, SS, SP, SEXP		S-38			S.275	
		C, 38-48	SL, SG	VFR, NS, NP			S-48		S.3	
2	R-2	A, 0-4	SL, Gr	VFR, NS, NP						3"
		Bt, 4-15	Clay, SBK	FI, SS, SP, SEXP					S.275	
		BC, 15-34	CL, WK SBK	FI, S, SP, SEXP		S-34			S.275	
		C, 34-48	SL, SG	VFR, NS, NP			S-48		S.3	
3	R-5	A, 0-4	SL, Gr	VFR, NS, NP						2"
		Bt, 4-18	Clay SBK	FI, S, SP, SEXP		S			S.275	
		BC, 18-35	CL, Wk SBK	FR, SS, SP, SEXP		S-35			S.3	
		B, 35-48	SL, Gr	VFR, NS, NP			S-48			
4	R-5	AE, 0-13	SL, Gr	VFR, NS, NP						2"
		Bt, 13-32	Clay, sBK	FI, S, SP, SExP		S			S.275	
		BC, 32-38	SCL, WK SBK	FR, SS, SP, SEXP		S-38			S.275	
		C, 38-48	SL, SG	VFR, NS, NP			S-48		S.3	

DESCRIPTION	INITIAL SYSTEM	REPAIR SYSTEM	SITE CLASSIFICATION (.0509): _____ suitable EVALUATED BY: _____ JH OTHER(S) PRESENT: _____
Available Space (.0508)	yes	yes	
System Type(s)	accepted	accepted	
Site LTAR	.275		
Maximum Trench Depth	24	24	

Comments: _____



Boring:	
ST	1200 Gallon
PT	1200 Gallon



12,500 ft² of Suitable Soils
24" TB, Accepted
0.275 LTAR
480 gal/day

GRAPHIC SCALE
1" = 50'



- *Keep tanks and drain lines 10' from property lines.
- *Not a survey.
- *Not a guarantee of a septic permit.
- *Keep supply lines >5' from property lines.
- *Some lines are flagged longer in the field than lengths indicate.
- *No grading septic area.
- *No adding soil within septic area
- *No rutting-up septic area
- *No cuts of >2' within 15' of septic areas

Central Carolina Soil Consulting, PLLC 1900 South Main Street, Suite 110 Wake Forest, North Carolina 27587 Phone (919)569-6704 Fax (919)569-6703	4-Bedroom Soils Map Lot 14, Lennox Manor Subdivision Wake County, North Carolina	Job#: 5387
		Drawn By: JH
		Date: 1/18/26
		Revision: 2/11/26



Central Carolina Soil Consulting, PLLC
1900 South Main Street, Suite 110, Wake Forest, NC 27587
Office Number: 919-569-6704

Acknowledgment of Subsurface wastewater evaluation and septic design by Central Carolina Soil Consulting, PLLC. for Lennox Manor lot 14,
for issuance of an IP and CA.

For Improvement Permit (IP) issuance:

“The LSS/LG evaluation(s) attached to this application is to be used to issue an Improvement Permit in accordance with G.S. 130A-335(a2) and (a3).”

For Construction Authorization (CA) issuance:

“The plans or evaluations attached to this application are to be used to issue a Construction Authorization in accordance with G.S. 130A-335(a2), (a5) and (a6).”

The LSS evaluation attached to this application was used to produce and design a subsurface wastewater septic system for permitting to obtain an IP and CA in accordance G.S. 130A-335(a2), (a3), (a5) and (a6).

Owner: RHAPSODY PROPERTY GROUP LLC

Owner's representative: Santiago E Aguilar, MANAGER

Date: 2/11/2026