

CEB 210

3513
COLDWATER
C 26714
150000

3513

(3513)

Out ~ 10'

2000

3400

100 x 100

1100

11-11-11

5

191

11

15

11

10. MUST BE

V

15H 201/

21.000

CONF. DAVIS

10

100

Zoning R30 By KAS
 Approve X Date 7-1-15
 Revises X Use 101A
 Reject 30 MBL 30
 Front 10 Rear 30
 Side 10 Corner 30
 Comments: SFD

1-11-75
Sps - 104
Total
of COASTAL

6000

2707147363

I certify that the location of planned or existing structure(s) are accurately shown. I understand failure to locate structure(s) accurately shown. I understand (s) permission to relocate in accordance with structure(s) grant of entry require the completion. I heretby grant the right of entry to make evaluations of inspections upon this property.

[Signature]
Signature of Owner or Authorized Agent

RFV 155A

313207

2006/07/07

Used CA Part B

Revised CH

1201500

WAKE COUNTY DEPARTMENT OF ENVIRONMENTAL SERVICES WELL AND SEWAGE SITE LOCATION PERMIT
NO PERMIT(S) FOR CONSTRUCTION, LOCATION OR RELOCATION ACTIVITY SHALL BE ISSUED
UNTIL AN AUTHORIZATION FOR WASTEWATER SYSTEM CONSTRUCTION HAS BEEN ISSUED
PERMIT VOID IF NOT IN COMPLIANCE WITH ZONING REGULATIONS AND/OR IF SITE IS ALTERED OR INTENDED USE CHANGED

PERMIT#: D052967 STATUS: A APP. DATE: 04/17/2015 BLDG. PERMIT#: 0152923
PIN: 2707 14 7363 000 TAX MAP: 0365 0000 JURISDICTION: WC ZONING: R30 SW DEVICE: N S#:
TOWNSHIP: 09 LITTLE RIVER APPLICANT: KIRBY MARSHBURN BLDG CORP (919) 422 - 7587
6901 LAKE MYRA RD WENDELL, NC 27591
HD USE: 101A CONVENTIONAL ONE-FAMILY HOUSE EXIST USE: DESIGN FEE REQ?: PAID?
LTAR: 0.30 BEDROOMS: 3 BASEMENT: N #EMPLOYEES: 0 FOUNDATION DRAIN: Y
SITE: ADDRESS: 3513 COLDWATER CREEK DR SUBDIVISION: COLDWATER CREEK LOT: 14 ACRES: 0.74 EASEMENT: N LOC: SYS:
DIRECTION: 264E L HWY 96 R PEARCES L FERRELL L COLDWATER

IMPROVEMENT PERMIT

[] As per GS 130A-335 (f), Improvement Permit is based on a Site Plan and is void Sixty (60) months from date of issuance.
[X] As per GS 130A-335 (f), Improvement Permit is based on a Plat and is valid without expiration.

Permit is subject to revocation if the site plan or plat, whichever is applicable, or the intended use changes.

TANK SIZE: 1000 gal. PUMP TANK: gal. GREASE TRAP: gal. SQ. FT. 900 ACCEPTED STATUS MAX DEPTH LINE: 18 in.
WASTEWATER: INDIVIDUAL SEWAGE: DOMESTIC TYPE SYSTEM: II A PUMP: N P/M: N L.P. TD: REDUCE: 35%
COMMENTS: IP ISSUED FOR 3BR/360GPD SFD ACCEPTED STATUS SYSTEM WITH 25% REDUCTION.
IP ISSUED? Y DATE: 07/07/2015 BY: (REH) *James H. Jordan* PHONE#: (919)-594-3069

AUTHORIZATION FOR WASTEWATER/WATER SYSTEM CONSTRUCTION VALIDITY CONCURRENT WITH THE IMPROVEMENT PERMIT

AUTHORIZATION CONDITIONS:

Contractors shall install system on contours, see attached site plan for wastewater system design and well location. No underground utilities, water lines or sprinkler systems may be located in the original system or repair areas. A septic tank filter with a riser for access is required. The wastewater system shall not be covered or placed into use until inspected by the Wake County Department of Environmental Services and an Operation Permit issued. An Accepted Status System may be used in place of conventional system, if it can be placed in the permitted/authorized trench footprint (except reduction in line length and/or number as allowed for in approval) and the installation is in accordance with the accepted system approval, without unauthorized product alteration. If permit required use of an Accepted Status System, substitution with another accepted status system may be made, as long as no changes are necessary in the location of each nitrification line (including any increase in line length), trench depth or effluent distribution method. If changes are necessary, prior approval by this office is required before system installation.

OTHER CONDITIONS: 3(15'X3') LINES OF GRAVITY 0.3 LTR AND 18" TRENCH BOTTOM, 1000GAL TANK, MAINTAIN 50' FROM NEIGHBORING WELLS AND 10' FROM PROPERTY LINES, INSTALL ON CONTOUR USING CARE NOT TO DISTURB SOIL, MAINTAIN AT LEAST 10' SEPARATION FROM ROAD CUT.

TANK SIZE: 1000 gal. PUMP TANK: gal. GREASE TRAP: gal. SQ. FT. 900 ACCEPTED STATUS MAX DEPTH LINE: 18 in.
MAINT: N OPER: N L/O: Y TRENCH#: 3 LENGTH: 100 ft. WIDTH: 36 in. DESIGNER: gal/min DOSE VOLUME: gal. PRETREATMENT: NA
DESIGN FLOW: gal/min DOSE VOLUME: gal. PRETREATMENT: NA
CA ISSUED? Y DATE: 07/07/2015 BY: (REH) *James H. Jordan* PHONE#: (919)-594-3069

CA consists of Parts A & B.

WAKE COUNTY DEPARTMENT OF ENVIRONMENTAL SERVICES WELL AND SEWAGE SITE LOCATION PERMIT
NO PERMIT(S) FOR CONSTRUCTION, LOCATION OR RELOCATION ACTIVITY SHALL BE ISSUED
UNTIL AN AUTHORIZATION FOR WASTEWATER SYSTEM CONSTRUCTION HAS BEEN ISSUED
/IT VOID IF NOT IN COMPLIANCE WITH ZONING REGULATIONS AND/ OR IF SITE IS ALTERED OR INTENDED USE CHANGED/

APPLICANT: KIRBY MARSHBURN BLDG CORP
6901 LAKE MYRA RD
WENDELL, NC 27591
HD USE: 101A CONVENTIONAL ONE-FAMILY HOUSE
LTA#: 0.30 BEDROOMS: 3 BASEMENT: N #EMPLOYEES: 0
ADDRESS: 3513 COLDWATER CREEK DR
SUBDIVISION: COLDWATER CREEK LOT: 14
DIRECTION: 264E L HWY 96 R PEARCES L FERRELL L COLDWATER
APPLICANT: 09 LITTLE RIVER
JUNSHIP: 2707 14 7363 000
TAX MAP: 0365 0000
JURISDICTION: WC
AP. DATE: 04/17/2015
BLDG. PERMIT#: 0152923
RECORDED: Y ORIG. PERMIT#: 0
ZONING: R30 SW DEVICE: N S#:

Well System: WATER: INDIVIDUAL - TYPE: NEW

WELL LOG INFORMATION: DEPTH: CASING DEPTH: YIELD: PUMP CONTRACTOR: REG.#
WELL CONTRACTOR: REG.#
GROUT APPROVED DATE DATE DATE
WELLHEAD APPROVED DATE DATE DATE
SYSTEM FINIALIZED DATE DATE DATE
COMMENTS: WELL LOCATION MUST BE EXACTLY 27' FROM BACK CORNER PROPERTY, 10' FROM EITHER SIDE PROPERTY LINE. THIS IS TO MAINTAIN 50' SEPARATION FROM NEIGHBORING REPAIR AREAS. CASE TO 35' AND RECOMMEND GROUTING TO 35' CALL WCES WITH QUESTIONS PRIOR TO DRILLING.

Operation Permit
DESIGN FLOW: gal/min. ACTUAL FLOW: DOSE VOLUME: gal. INNOVATIVE LETTER:
INSTALLATION APPROVED BY: TYPE SYSTEM: II A
COMMENTS:

OPERATIONS PERMIT ISSUED? BY: *****
Systems defined as either a Type IIIb, IIIg with a pump, IV, V or VI, in accordance with the North Carolina Administrative Code 15A NCAC 18A .1961, Table V as adopted by reference in the "Regulations Governing Wastewater Treatment and Dispersal Systems in Wake County", require Wake County Environmental Services to conduct periodic inspections on this type system, pursuant to 15A NCAC 18A .1961 (j). Fees for these inspections will be charged as per the approved Fee Schedule. In addition, all systems are to be operated and maintained as specified in 15A NCAC 18A .1961. This permit is based in part on information provided by the homeowner or his/her representative in the application submitted for this permit. The Environmental Health Specialist is not responsible for false or misleading information contained in this report that may have resulted from false or misleading statements provided to him in the application. Neither Wake County nor the Environmental Health Specialist warrants that the septic tank system will continue to function satisfactorily in the future or that the water supply will remain potable.

As Built Information:

Date: _____
ST: _____ gals
PT: _____ gals
GT: _____ gals
D-box/FD/PM elev.: _____ ft.
Supply Line: _____ ft.
D.O.M.: _____
D.O.M.: _____
D.O.M.: _____
Rod reading: _____
Distance to Structure: _____
Distance to Well: _____
Distance to P/L: _____
Pretreatment: _____
Filter: _____
Line 1: _____ Date: _____
Line 2: _____ Date: _____
Line 3: _____ Date: _____
Line 4: _____ Date: _____
Line 5: _____ Date: _____
ETM1: _____
CC1: _____
ETM2: _____
CC2: _____
OR: _____
AC: _____
WM: _____
Notes: _____