

IMPROVEMENT PERMIT

Granville Vance Public Health
Environmental Health
P.O. Box 367
Oxford, NC 27565
Phone: (252) 492-5263 Fax: (252) 492-2361

For Office Use Only

*CDP File Number 470023 - 1
County ID Number: 0600B04005
Evaluated For: NEW

PERMIT VALID UNTIL: 04/15/2031

***NOTE TO INSPECTIONS DIVISION:** Building Permits cannot be issued with this Improvement Permit.

Applicant: Worth Taylor Const. Co.

Address:

City: Henderson

State/Zip: NC 27537

Phone #:

Property Owner: Douglas Snoddy

Address:

City:

State/Zip:

Phone #:

Property Location & Site Information

Address: Country Lake Rd Henderson, NC 27537 Subdivision: Kerr Lake Estates Block/Phase: NEW Lot: 29

Directions

See attached

Road #:

Structure: SINGLE FAMILY

of Bedrooms: 3

of People: 6

*Water Supply: NEW WELL

System Specifications

Initial System

Usable Soil Depth:

Design Flow: 360

Soil Application Rate: 0.3000

*System Classification/Description:

Type IIIg - Other Non-Conventional Systems

*Proposed System:

LOW PROFILE

Minimum Trench Depth: _____ Inches

Maximum Trench Depth: 8 Inches

Septic Tank: 1000 Gallons

Pump Required: ☐ Yes ☐ No ☒ May Be Required

Pump Tank: 1000 Gallons

Repair System Required: ☒ Yes ☐ No ☐ No, but has Available Space

Repair System

Usable Soil Depth:

Soil Application Rate: 0.300

*System Classification/Description:

Type IIIg - Other Non-Conventional Systems

*Proposed System: DRIP

Minimum Trench Depth: _____ Inches

Maximum Trench: Depth: 8 Inches

Pump Required: ☐ Yes ☐ No ☒ May Be Required

Pump Tank: _____ Gallons

No grading or construction activity is allowed in areas designated for system and repair without approval of Health Department.

*Site Modifications

The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements.

*Permit Conditions

House cannot be moved any further back on the property. Back of House is currently 92ft from the road. If a porch is to be built on the back house will need to be moved closer to the road.

The Department and Local Health Department may impose conditions on the issuance and may revoke the permits for failure of the system to satisfy the conditions, the rules, or this article. This permit is subject to revocation if the site plan, plat, or intended use changes (NCGS 130A-335(f)). The person owning or controlling the system location, installing, operation, maintenance, monitoring, reporting, and repair (per rule .0301(a)).

Authorized State Agent:

Diamond, Chris




Date of Issue:

04/15/2026

Total Time: (HH:MM)

☐ Hand Drawing☐ Import Drawing****Site Plan/Drawing attached.****

____ : ____



Construction Authorization

Granville Vance Public Health

Environmental Health

P.O. Box 367

Oxford, NC 27565

Phone: (252) 492-5263 Fax: (252) 492-2361

For Office Use Only

*CDP File Number: 470023 - 1

County ID Number: 0600B04005

Evaluated For: NEW

PERMIT VALID UNTIL: 04/15/2031

☐ Open Pump System Sheet

Applicant: Worth Taylor Const. Co.

Address: [REDACTED]

City: Henderson

State/Zip: NC 27537

Phone #: [REDACTED]

Property Owner: Douglas Snoddy

Address: [REDACTED]

City: [REDACTED]

State/Zip: [REDACTED]

Phone #: [REDACTED]

Property Location & Site Information

Address/Road #: Country Lake Rd Henderson, NC 27537

Subdivision: Kerr Lake Estates

Phase: NEW Lot: 29

Directions:

See attached

Structure: SINGLE FAMILY

of Bedrooms: 3

of People: 6

*Water Supply: NEW WELL

System Specifications

Usuable Soil Depth: [REDACTED]

Design Flow: 360

Soil Application Rate: 0.3000

*System Classification/Description:

Type IIIg - Other Non-Conventional Systems

*Proposed System:

LOW PROFILE

Minimum Trench Depth: [REDACTED] Inches

Maximum Trench Depth: 8 Inches

Minimum Soil Cover: 6 Inches

Maximum Soil Cover: 8 Inches

*Distribution Type: GRAVITY - SERIAL

Septic Tank: 1,000 Gallons

Pump Required: ☐ Yes ☐ No ☒ May Be Required

Pump Tank: 1,000 Gallons

Grease Trap: [REDACTED] Gallons

Nitrification Field: 1200 Sq. ft.

No. Drain Lines: 4

Total Trench Length: 400 ft.

Trench Spacing: 9 - [REDACTED]

Trench Width: 3 - [REDACTED]

Aggregate Depth: [REDACTED] inches

☐ Inches O.C.

☒ Feet O.C.

☐ Inches

☒ Feet

Septic Tank Installer

Grade Level Required:

☐ I

☐ II

☐ III

☐ IV

The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements.

*Permit Conditions:

House cannot be moved any further back on the property. Back of House is currently 92ft from the road. If a porch is to built on the back house will need to be moved closer to the road.

The Authorization for Wastewater System Construction shall be valid for a period equal to the period of validity of the Improvement Permit and may be issued at the same time the Improvement Permit issued (NCGS 130A-336(b)). If the installation has not been completed during the period of validity of the Construction Permit, the information submitted in the application for a permit or Construction Authorization shall become invalid, and may be suspended or revoked (.0204(k)(1)). The person owning or controlling the system shall be responsible for assuring compliance with the laws, rules, and permit conditions regarding system location, installation, operation, maintenance, monitoring, reporting and repair (per rule .0301((a))).

Authorized State Agent: Diamond, Chris

Date of Issue: 04/15/2026

Site Plan/Drawing attached.

Total Time : (HH:MM)

☐ Hand Drawing

☐ Import Drawing

Granville-Vance Dist. Health Department
Environmental Health

File _____

Permit Number 470023

8 Improvement Permit

8 Construction Authorization

SITE SKETCH
ON-SITE / WELL

Worth Taylor Const. Co
Applicants Name

Country Lake Rd
Address

Kerr Lake Estates Lot 29
Subdivision -- Section -- Lot

Chris R. [Signature]
Authorized State Agent

4-15-26
Date

System components represent approximate contours only. The contractor must flag the system prior to beginning the installation to ensure that proper grade is maintained.

- At Grade System
- No Grading or Construction Activities on Septic Area

P/L

