

Environmental Services - Water Quality
Onsite Wastewater Scan Data Entry Form

PERMIT #: **D 0 2 5 5 7 9**

PIN #: **0 6 4 7 9 0 5 8 6 2**

OP DATE: **1 1 / 2 2 / 2 0 0 2**

SYSTEM USE:

- ☒ House
☐ Mobile Home
☐ Business
☐ Other

SEWAGE TYPE:

- ☒ Domestic
☐ Industrial

PUMP/SIPHON?:

- ☐ Yes
☒ No

PRESSURE MANIFOLD:

- ☐ Yes
☒ No

SYSTEM TYPE:

- ☐ I
☒ II
☐ III
☐ IV
☐ V
☐ VI
☐ Other

SUB TYPE:

- ☐ A
☒ B
☐ C
☐ D
☐ E
☐ F
☐ G

NBR BEDROOMS:

- ☐ 1
☐ 2
☒ 3
☐ 4
☐ 5
☐ 6
☐ Other

MAINT. SCHEDULE:

- ☐ Yes
☒ No

CERT. OPERATOR

- ☐ Yes
☒ No

GT ST PT SIZE

- | | | | |
|-------------------------------------|-------------------------------------|-------------------------------------|------------------|
| ☐ | ☐ | ☐ | 750 |
| ☐ | ☐ | ☐ | 900 |
| ☐ | ☒ | ☐ | 1,000 |
| ☐ | ☐ | ☐ | 1,200 |
| ☐ | ☐ | ☐ | 1,500 |
| ☐ | ☐ | ☐ | 1,800 |
| ☐ | ☐ | ☐ | 2,100 |
| ☐ | ☐ | ☐ | 2,500 |
| ☐ | ☐ | ☐ | 3,000 |
| ☐ | ☐ | ☐ | 4,000 |
| ☐ | ☐ | ☐ | 5,000 |
| ☐ | ☐ | ☐ | 8,000 |
| ☐ | ☐ | ☐ | 10,000 |
| ☐ | ☐ | ☐ | Other |
| ☒ | ☐ | ☒ | None/NA GT or PT |

DRAINFIELD SIZE(SQ. FT.)

0 0 9 2 0

DRAIN TYPE:

- ☐ Stone
☐ EZ Flow
☐ Infiltrator
☐ Biodiffuser
☐ Cultec
☐ Drip
☐ Hancor
☐ Large Dia. Pipe
☐ Multi-Pipe
☒ Other

MAX DEPTH (IN.):

- ☐ 12 in. or less
☐ 18 in. or less
☐ 24 in. or less
☐ 26 in. or less
☐ 28 in. or less
☒ 30 in. or less
☐ 32 in. or less
☐ 36 in. or less
☐ Other

STONE DEPTH (IN.):

- ☐ 8 in. or less
☒ 12 in. or less
☐ 18 in. or less
☐ 24 in. or less
☐ Other

TRENCHES:

- ☒ Individual
☐ Bed

TRENCH WIDTH (IN.):

- ☐ 12 in. or less
☐ 18 in.
☐ 24 in.
☒ 36 in.
☐ 6 ft. or less
☐ 9 ft. or less
☐ Other

WAKE COUNTY DEPARTMENT OF ENVIRONMENTAL SERVICES WELL AND SEWAGE SITE LOCATION PERMIT

NO PERMIT(S) FOR CONSTRUCTION, LOCATION OR RELOCATION ACTIVITY SHALL BE ISSUED

UNTIL AN AUTHORIZATION FOR WASTEWATER SYSTEM CONSTRUCTION HAS BEEN ISSUED

PERMIT VOID IF NOT IN COMPLIANCE WITH ZONING REGULATIONS AND/ OR IF SITE IS ALTERED OR INTENDED USE CHANGED

PERMIT#: D025579 STATUS: A APP. DATE: 10/15/2002 BLDG. PERMIT#:
PIN: 0647.04 90 5862 000 TAX MAP: 0836 0000 RECORDED: Y ORIG. PERMIT#:
TOWNSHIP: 12 MIDDLE CREEK JURISDICTION: WC ZONING: R30
APPLICANT: POOLS, RISING SUN
5608 HILLSBOROUGH ST
RALEIGH, NC 27606
(919) 851 - 9700
USE: HD USE: 0002 VERIFY/EXISTING SYSTEM
EXIST USE: 101 ONE-FAMILY HOUSE
DISPOSAL: BEDROOMS: 3 BASEMENT: N #EMPLOYEES: 0 FOUND DRAIN: N
SITE: ADDRESS: 6616 WAVCOTT DR
SUBDIVISION: PRESCOTT DOWNA LOT: 89 ACRES: 1.55
DIRECTION: 401 S HWY 42 R PINEY GROVE WILBON RD
RT ONTO WAVCOTT

IMPROVEMENT PERMIT

TANK SIZE: EXIST gal. PUMP Tank: ____ gal. SQ FT: 920 STONE DEPTH: 12 in. MAX DEPTH LINE: 30 in.
WASTEWATER: INDIVIDUAL SEWAGE: DOMESTIC TYPE SYSTEM: II B PUMP: N P/M: N
DAILY FLOW: 360 gal/day DESIGN FEE REQ?: N PAID?: N WATER: INDIVIDUAL

COMMENTS:

IP ISSUED? Y DATE: 02/11/2000 BY: (MTB)  PHONE#: 856-7433

AUTHORIZATION FOR WASTEWATER/WATER SYSTEM CONSTRUCTION

VOID SIXTY (60) MONTHS FROM DATE OF ISSUANCE

AUTHORIZATION CONDITIONS:

Contractors shall install system on contours, see attached site plan for wastewater system design and well location. No underground utilities, water lines or sprinkler systems may be located in the original system or repair areas. A septic tank filter with a riser for access is required. The wastewater system shall not be covered or placed into use until inspected by the Wake County Department of Environmental Services and an Operation Permit issued. **OTHER CONDITIONS:**

INSTALL LINES AS SHOWN. MAINTAIN 6' SEPERATION FOR UPPER LINE AND LOWER LINE OF EXISTING SYSTEM. KEEP ENTIRE SYSTEM GREATER THAN 15' FROM POOL CAVITY. KEEP POOL DECK AT LEAST 5' FROM SYSTEM. DO NOT DRIVE ON SYSTEM OR REPAIR AREA. ENCASE PIPE FROM TANK TO D-BOX WITH SCHEDULE 80 PVC. ROPE OFF DRAINFIELD AFTER INSTALLTION TO PREVENT TRAFFIC ON SYSTEM. CALL PRIOR TO INSTALLATION WITH ANY QUESTIONS OR CHANGES. OPERATION PERMIT MUST BE ISSUED PRIOR TO COMMENCEMENT OF ANY POOL CONSTRUCTION.

TANK SIZE: EXIST gal. PUMP TANK: ____ gal. SQ FT: 920 STONE DEPTH: 12 in. MAX DEPTH LINE: 30 in.
MAINT: N OPER: N L/O: N TRENCH#: 4 LENGTH: 80 ft. WIDTH: 36 in. DESIGNER: ____
SUBFIELDS: ____ DESIGN HEAD PRESSURE: ____ DESIGN FLOW: ____ gal/min DOSE VOLUME: ____ gal.

CA ISSUED? Y DATE: 10/24/2002 BY: (MTB)  PHONE#: 856-7433

Copy 10/11/02

0647.04 905862 Britt

⊗ cust wants to move LINES to this if possible
50' Colonial facade

HAZ.

SITE PL
R1001850

A200.0

new set
#90.30

10'S
if move near

TANK house

15' TANK

Zoning R30 By DMC
Approved ✓ Date 03-30-99
Revised ✓ Use 101 1-14-2000
Reject MBL
Front 30 Rear 30
Side 10 Corner 30

Comments: 30'R SETBACK
CONTAIN WITHIN FLOOD SOIL

6616 WANCOTT DR

INSCOTT LN

Rept 51038

1.553 ac.

Lot # 89 Prescott Downs ✓

Rept 51038

I certify that the location of planned or existing structures are accurately shown. I understand that the structures in accordance with this plat may require the relocation of structures, regardless of degree of completion. I hereby give permission to the Municipality to have the right of entry in their evaluations or inspections upon this property.

Signature of Owner or Authorized Agent

P.004-00

TO: 9199570301

HAZ. SITE P. 12/18/85

REPAIR AREA

10'S

15'

15' TAN

house

AVCOTT DR

INSCOTT LN