

QUOTE

Smith and Sons LLC

DATE February 20, 2025

Anthony Smith OWNER
Raleigh, NC 27604
(919) 618- 0107
Smithanthony319@yahoo.com

TO: Helen Headington
4946 Glenridge Drive,
Raleigh, NC 27604

919-356-4040 **UPDATED**

Heleneheadington10@gmail.com

	JOB	All 11	DUE DATE
Anthony Smith		½ at start and ½ when complete	

JOB DESCRIPTION	LABOR PRICE	MATERIAL PRICE
Flooring 1,000 sq. ft.	\$ 3,300.00	
Demo all tile in kitchen, thresholds to ensure a level-flat transitions throughout the property. Prep to accept new flooring (LVP)	600.00	Material price included
Paint cabinets, wipe down existing cabinets with degreaser to remove all dirt and grease. Remove all knobs on doors, and drawers, sand all areas. Paint all doors 20 total paint all drawers 16 total with 36 total.		
Install all new hardware. Will tape up all hinges to make sure they can be re-used if wish. Will use Sherman Williams cabinetry paint	\$ 2,600.00 paint included in quote	HO will provide hardware
Paint entire inside walls, trim ceilings. Repair any damage in walls & ceilings. Go thru each wall for any nail holes, cracks or damage and fix everything if found. Fill all nail holes etc. Paint wall 2 coats. Paint trim semi-gloss (white) will wipe down all baseboards so no dirt will be painted over. Caulk all trim etc. if needed to make a clear line for paint	\$4,500.00	Paint included
- Install 3 doors, kitchen side door, back door, and side door. - For 3 door install. All trim will be install (new) painted. As well as floor plates	875.00	
Hall bathroom: Demo floor remove tile	300.00	

• Install 40 ft. flooring • Pull toilet and reset toilet with new wax ring	600.00	HO to provide flooring
• Replace soft area on floor	285.00	
• Remove all rotten area. Install new piece of subfloor. Remove old rotten area, cut out ¾" subfloor or what calls for.	100.00	
• Remove old tub drain and shower faucet for new plumbing to fit the new kit.	185.00	
• Install new plywood on floor	200.00	
• Install new plumbing.	295.00	HO to provide new faucet/tub
• Install new trim thru the bathroom	215.00	Included
• Paint – the vanity the color of HO choice. Install new hardware, knobs etc.	150.00	HO to pick color
• Master Bathroom: Full demo of the floor	300.00	
• Install 2 pieces of plywood • Install 40 sq. ft. of flooring	200.00 600.00	
• Paint and change out faucet in bathroom vanity	225.00	HO to supply faucet
• Repair sheetrock in master bathroom, mud, sand, tape prep for paint.	Included	
• Install ¾" Luon to accept the new flooring height.	\$250.00	\$ 250.00
• Total	\$ 16,030.00	

prepared by: Anthony Smith of Smith and Son, Raleigh, NC 27604, (919) 618- 0107, AnthonyLSmith1216@gmail.com

This is a quote of the services named above. Conditions and terms are subject to discussion by both parties. If terms are agreed upon a contract will be drawn up stating all the terms and agreement of the services, conditions, and prices.

To accept this quotation, sign here and return: _____

THANK YOU FOR YOUR BUSINESS!:

