CHILL BROTHERS

Chill Brothers, LLC.
3131 RDU Center Drive, Ste 103
Morrisville, NC 27560

(866) 424-4552
License # 30223 H2/ H3 Class 1

BILL TO
Robert Bolduc
920 Merwin Road
Raleigh, NC 27606 USA

ESTIMATE	ESTIMATE DATE
83111735	Mar 21, 2025

JOB ADDRESS
Robert Bolduc
920 Merwin Road
Raleigh, NC 27606 USA

Job: 2052281
Technician: Julius Thomas

ESTIMATE DETAILS

Robert Bolduc: We are doing a 3 ton horizontal gas Lennox diamond communicating R454B 90%. This system is for upstairs.

Cut in new hole for roof jack and flue

electrical work for upstairs both electrical panels and upsizing one fuse

run new drain lines from inside to outside the house

new gas line to be run

adding 15 supply with grille cover

Adding 3 new returns with grille and cover

Air leak test for existing duct runs

Thermostat
Extended Labor Warranty (10 Year Parts/ 10 Year Labor Warranty)
filter media cabinet

Exterior: Replace Electrical Disconnect Box, Electrical Whip, Condenser Pad (as needed), Armaflex Condenser Lines, Filter Drier on Line Set, add Surge Protection. Evacuate old refrigerant and purge line with nitrogen.

Interior: Replace Return Plenum, Furnace stands, Gas Flex House, Exhaust Flute up to Roof Jack, Drip Pan, Float Safety Switch, Drain Lines Connecting to the Evap Coil, Supply Plenum, Add Adjustable Dampers/Collars.

Conduct Pre-Install, Install, and Post-Install Appointments

This system is for downstairs

We are doing a 1.5 ton vertical gas Lennox gold R454B

Add 3 new duct runs

we are disconnecting the duct runs that are running upstairs and blocking off with spray in foam

add T6 thermostat downstairs

No Thermostat
Extended Labor Warranty (10 Year Parts/ 10 Year Labor Warranty)
filter media cabinet

Exterior: Replace Electrical Disconnect Box, Electrical Whip, Condenser Pad (as needed), Armaflex Condenser Lines, Filter Drier on Line Set, add Surge Protection. Evacuate old refrigerant and purge line with nitrogen.

Interior: Replace Return Plenum, Furnace stands, Gas Flex House, Exhaust Flute up to Roof Jack, Drip Pan, Float Safety Switch, Drain Lines Connecting to the Evap Coil, Supply Plenum, Add Adjustable Dampers/Collars.

Conduct Pre-Install, Install, and Post-Install Appointments
2,000 Rebates Applied. (BBP)

SERVICE	DESCRIPTION	QTY	PRICE	TOTAL
TIO- iHarmony Zone System	TIO- iHarmony Zone System: Mixing box and or Plenum Installation Note: Does not include sheetrock repair Includes: 10C16 iHarmony Dampers Dampers 19V30 S30 Tstat 17A30 Zone Sensor 10P87 Transformer (or capatible) Plenums Plenums/Mixing boxes BB Supplies (wire, tapes, seals)	1.00	$6,825.00	$6,825.00
TIB-LEN-214619573	Diamond Comm 3t Gas, Horz (214619573): **Elite 18 Var Cap Gas, 3 Ton** **Install Package includes: Installation/Replacement of Equipment, from plenum to plenum (line sets will only be replaced when needed and may incur an extra charge).**	1.00	$0.00	$0.00

	Does not include replacement or repair of ductwork (flex, hard pipe, wyes, mixing boxes, etc.) **Attic Stair replacement/repair due to size of new equipment is an added charge.** **Note:** Equipment may be replaced upon availability; it will be replaced to obtain the same seer rating and quality and/or upgraded for the same price - AHRI certified			
TIB-LEN-214633159	Gold Plus 1.5t Gas, Vert (214633159): **Merit 17 Gas 1 Stg AC + 1 Stg Heat (MS ECM Furnace)(Vertical Coil), 1.5 Ton** **Install Package includes: Installation/Replacement of Equipment, from plenum to plenum (line sets will only be replaced when needed and may incur an extra charge).** **Does not include replacement or repair of ductwork (flex, hard pipe, wyes, mixing boxes, etc.)** **Attic Stair replacement/repair due to size of new equipment is an added charge.** **Note:** Equipment may be replaced upon availability; it will be replaced to obtain the same seer rating and quality and/or upgraded for the same price - AHRI certified	1.00	$0.00	$0.00
TSS-GEN-ELEC61	Install T6 pro Wifi Thermostat: Install T6 pro Wifi Thermostat	1.00	$578.76	$578.76
TIO-Install Duct Run	TIO-Installation of Duct Run: Duct Run replacement or addition (up to 25ft per duct run); Includes collars, duct, labor and material Note: Duct Run is from plenum to mixing box (wye) -OR- Plenum to Grille. Grilles, register boxes, plenums, triangles, wyes are an additional cost	18.00	$460.00	$8,280.00
Hvac System Discount	Hvac System Discount: Hvac System Discount	1.00	$6,879.24	$6,879.24
EIC-LEN-78W69 Lennox SL280UH090V36B	SL280UH090V36B Lennox Furnace 80% 3.0 Ton	1.00	$7,760.00	$7,760.00
EIW-GEN-LABAC10YR Cool Care	Cool Care Labor Warranty - AC - 10 years	1.00	$1,401.00	$1,401.00

EIC-LEN-19K14	EL18XCVS036-230 Lennox Condenser 3.0 Ton	1.00	$11,686.00	$11,686.00
Lennox EL18XCVS036-230				
EOP-LEN-Y2920	HCC16-28 Lennox FMC 17.5 x 28.5 x 7 w/M13	1.00	$643.00	$643.00
Lennox HCC16-28				
EIC-LEN-Y8736	RFGF05E-3.0-747 Sanhau TXV 3.0 Ton	1.00	$224.00	$224.00
Sanhau RFGF05E-3.0-747				
EIP-LEN-22V24	S40 Lennox Thermostat 3h/2c	1.00	$2,798.00	$2,798.00
Lennox S40				
EIC-LEN-25R25	CK40HT-42B Lennox Coil Horizontal 3.5 Ton Refrigerant Versatile	1.00	$4,085.00	$4,085.00
Lennox CK40HT-42B				
EIC-LEN-81W21	ML180UH045E36A Lennox Furnace 80% 3.0 Ton	1.00	$5,120.00	$5,120.00
Lennox ML180UH045E36A				
EIW-GEN-LABAC10YR	Cool Care Labor Warranty - AC - 10 years	1.00	$1,401.00	$1,401.00
Cool Care				
EOP-LEN-Y2920	HCC16-28 Lennox FMC 17.5 x 28.5 x 7 w/M13	1.00	$643.00	$643.00
Lennox HCC16-28				
EIC-LEN-23A64	ML17XC1-018-230 Lennox Condenser 1.5 Ton	1.00	$7,486.00	$7,486.00
Lennox ML17XC1-018-230				
EIC-LEN-25M67	CK40CT-24A Lennox Coil Upflow 2.0 Ton Refrigerant Versatile	1.00	$4,189.00	$4,189.00
Lennox CK40CT-24A				

POTENTIAL SAVINGS	$96.46
SUB-TOTAL	$69,999.00
TAX	$0.00
TOTAL	$69,999.00

We are honored that you have chosen CHILL BROTHERS as your Cooling and Heating service company.

CUSTOMER AUTHORIZATION


Chill Brothers, LLC.; once signed by the Customer it becomes a contract/invoice.

Please note that any and all special discounts including the buyback program have been applied to the above pricing.

Terms for non-financed equipment installations require a 50% deposit, and the remaining balance is due in full on the day of the installation; the install are instructed NOT to connect the system unless payment is received in full.

You, the buyer, may cancel this transaction, without any penalty or obligation, within three (3) business days from the signed estimate date; you must do so in writing; if you wish to cancel, call 832.478.7777 or your Comfort Advisor and ask for a "Notice of Cancellation".

Note: Fees may apply for ALL cancellations for any and all services applicable and a restocking fee and/or labor fees will be assessed if cancelled without written notice.

Sign here  Date 3/24/2025