# P. E. Teague, P.E., PLLC
2705 Waterloo Ct., Ral, NC 27613
Peteague50@gmail.com.com
(919)247-2572


April 8, 2020 (Lic. #P-0207)

To: Hunter Winstead

Subject: 3108 Brentwood Rd.
Raleigh, NC

To Whom It May Concern,

The following observations have been made on subject project after a site inspection has been conducted. A renovation project is taking place in the kitchen and family room. I recommend removing the ceiling joists and the wall that was supporting them. Then install 2x6 collar ties at 16" on center. The existing rafters now become a part of the vaulted ceiling. The vaulted rafters need to be furred down in order to install 1" baffle vents and the R38 insulation.

If you have any questions or additional issues arise, please feel free to call me at (919)247-2572.
Sincerely,

Patrick E. Teague, P.E.




04/08/20